

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Sr.DEE/Gen/BSL acting for and on behalf of The President of India invites E-Tenders against Tender No **BSL-L-W-T-40-2026** Closing Date/Time 03/06/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Establishing 2 X 5 MVA 33/11 KV Substation along with provision of new 33 KV express feeder for enhanced reliability of Power supply at Bhusawal.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	03/06/2026 15:00	Date Time Of Uploading Tender	07/05/2026 19:25
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	80509759.64	Tendering Section	ELECT.GEN.
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	1610200.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	20/05/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () I-(A) : 2 X 5 MVA 33/11 KV Substation							37529365.50	
1	Please see Item Breakup for details.				8811197.00	AT Par	8811197.00	
	Description:- Supply of 33 KV HT panel [2 (IC)+3 (OG)+ (1 BC)] AS per technical specification. 33 KV, 1250 A, 26.3 KA/ 3 SEC HORIZONTAL withdraw able VACUUM CIRCUIT BREAKER , WITH SPRING CHARGING MOTOR 230 VAC , CLOSING COIL & TRIPPING COILS RATED 110 V DC 4 NO + 4 NC, Handles for VCB, Current Transformer RATIO : /5 ACORE 1 : 10 VA, CL : 1.0CORE 2 : 10 VA, CL : 5P20 (Fixed type) (16 Nos.), Potential Transformer 33000V/3/110V/3/110V/3 CORE 1 : 50 VA, CL : 1.0 (Fixed type) (06 Nos.), Numerical relay having 3 O/ C+1 E/F PROTECTION RELAY, (50/51/50N/51N/95) (04 Nos), Numerical relay having 3 O/ C+1 E/F PROTECTION RELAY,(50/51/50N/51N/95/27/59) (02 Nos.), Arc Flash relay with 3 Sensor Arrangement (05 Nos.), Master Trip relay - Hand Reset (86) (06 Nos.), Auxiliary relay for transformer 3 Element (02 Nos.), Auxiliary relay Plug In type for Contact Multiplier 52X OTI/WTI/MOG & Transformer auxiliary relay operation (20 Nos.), Indication - {BREAKER ON - Red (06 Nos.), BREAKER OFF - Green (06 Nos.), AUTO TRIP INDICATION - Amber (06 Nos.), SPRING CHARGE HEALTHY - Blue (06 Nos), TRIP CIRUIT HEALTHY - White (06 Nos.), BREAKER TEST POSITION - Green (06 Nos.), BREAKER SERVICE POSITION - Red (06 Nos.), RYB INDICATION (Red / Yellow / Blue) (02 Nos.),} Metering - {Digital Multifunction meter Class 0.5 with RS485 Communication (05 Nos.), Digital ammeter (05 Nos.), Digital voltmeter (02 Nos.), Temp Sensor for Heat Riseing (12 Nos.)}, Standard Electrical Accessories - {DC ON/OFF SWITCH (06 Nos.), AC ON/OFF SWITCH (06 Nos.), 80W STRIP HEATER (06 Nos.), THERMOSTAT (06 Nos.), Door Limit Switch (06 Nos.), Toggle Switch (06 Nos.), CUBICLE ILLUMINATING LAMP (06 Nos.), 6A, 230V, 3 PIN PLUG & SOCKET (06 Nos.), 25 Amp trip - Neutral Close Type Breaker Control switch (06 Nos.), LOCAL/REMOTE SELECTOR SWITCH (05 Nos.), Annunciator with Accept/Reset/Test push button 16 W (05 Nos.), Hooter 96 X 96 (05 Nos.), MCB 10A, 2P, 110VDC, for DC circuit (06 Nos.), MCB, 10A, 240VAC, 2P for AC circuit (06 Nos.), MCB, 6A, 240VAC, 2P (06 Nos.), MCB 25 A, 4P MCB (06 Nos.), Fuse Link 2A/4A for CB control/Indication & PT secondary ckt. (02 Nos.), Spout & Shutter Assembly (06 Nos.), Power Pack 230 VAC - 110 VDC with 30 Min back up (06 Nos.), Surge Arrester Set of 3 for Incomer (02 Nos.), Inhouse Component - {Enclosure OUTDOOR Type (2 IC + 1 BC + 1BR + 3 OG) (07 Nos.), Suitable Busbar -Aluminium 80x10 x2 (07 Nos.), Earthing Busbar - Copper (07 Nos.), Wires other accessories (07 Nos.)}.							
2	Please see Item Breakup for details.				90764.00	AT Par	90764.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	Description:- Design, fabrication, erection, testing and commissioning of 33KV out door type, 1250 A triple pole, rotating type Air Break Isolator with earthing switch (Conforming to IS 1818/72 or latest complete in all respect) on isolators structure with suitable arrangement as required and as per direction of site-in-Charge.				
3	Please see Item Breakup for details. Description:- Supply, fitting, fixing of 33 KV, 400 Amps, 25 KA Air Break vertical mounting Gang operating switch. The Gang Operating Switch shall conform to the following standards: (i) IS-9920 (Part I to V) (ii) IS 2544/1973 (iii) IS2633. The Insulators should be 22 KV /24 KV class (for 33KV AB Switches) Post Insulators complete with pedestal cap duly cemented to be used in the AB Switch Set conforming to IS-2544/1973. The operating mechanism shall be suitable for manual operation from the ground level and shall be so designed that all the three phases shall open or close simultaneously. The Switches shall be robust in construction, easy in operation and shall be protected against over travel or straining that might adversely affect any of its parts. The required base M.S. Channel, phase coupling rod, operating rod with intermediate guide braided with flexible electrolytic copper, tail piece of required current carrying capacity and operating mechanism with ON' & OFF' positions shall be provided. The operating rod shall be medium gauge of 32mm diameter nominal bore G.I. pipe single piece 6 meters. The phase coupling rod for gang operation shall medium gauge 25mm dia nominal bore G.I. Pipe. Rotating post insulators shall be provided with suitable bearing mounted on a base channel with 6 mm thick thrust collar and 6mm split pin made out of stainless steel. The operating down rod shall be coupled to the spindle (minimum dia -32mm) for gang operation through another suitable bearing by two numbers 10mm dia through stainless steel bolts with double nuts. The post insulators should be fixed with the base channel using Galvanized Nuts and Bolts. Suitable arcing horns shall be provided for breaking the charging current horn shall be made of 10 mm dia G.I. Rod with spring assisted operation. The required Test certificates of the Gang operated switch should be provided	63340.00	AT Par	63340.00	
4	Please see Item Breakup for details. Description:- Supply, fitting, fixing of 33 KV Dropout fuse, 400Amps, 3 pole with 4Nos 22/24KV post insulator per phase. The Drop Out fuse unit shall conform to the following standards: (i) IS-5792-1973 (For high voltage expulsion fuses & similar fuses) (ii) IS-2544-1973 (for porcelain post insulators) (iii) IS-9385-1979 or its latest amendments if any. (iv) IS-2633-1979 (For Galvanization of ferrous parts). The Drop out Fuses shall have adjustable arcing horns made of solid copper rod having 8.23 mm dia. The horns shall be fitted with screwing devices with fly nuts for fixing and tightening the fuse wire. It shall have robust terminal connector 5s of size 80mm x 50 mm x 8mm made of copper casting (95% minimum copper composition) duly silver plated with two numbers of 12 mm dia brass bolts and double nuts with flat brass washers. The connector should be capable of connecting crimpable conductor upto 232 Sq.mm. size (ACSR/ AAC) with bimetallic solderless sockets .The Drop Out Fuse Set shall suitable for horizontal mounting on sub-station structures. . All metal (ferrous) parts shall be galvanized and polished. Only post insulator (original cemented and not pin insulators shall be used for the Drop Out Fuse Set.	32822.00	AT Par	32822.00	
5	Please see Item Breakup for details. Description:- Supply, installation, commissioning and testing of set of HT VCB panel board 250 MVA, 400/630 Amps capacity, degree of protection -P4x, consisting of : Incoming -02 nos, outgoing - 04nos, Buscoupler - 01Nos - 11 KV, 13.1 Ka, 3 pole Vacuum circuit breaker conforming to IS : 13118 (latest version) with PT having ratio of 11KV/110Volt AC, Electronic protection relay with 02 over current & 01 earth fault protections, electronic tri-vector meter and ammeter with selector switches, LED type indication lamps on 3 phases, busbar chamber with 3 phase copper busbars, strip type heater, double copper wound CTs and suitable cable end box, 24VDC, 135 AH battery set & single phase battery charger, VCB panels to be supplied as per technical specifications attached.	3275301.00	AT Par	3275301.00	
6	Please see Item Breakup for details. Description:- Supply, fabrication, fixing of MS channels and angles of sizes ISMC 150 x 75 mm x 6 mm and ISA 75 x 75 mm x 6 mm (or) any other dimension as per site condition, including necessary clamps, bolts, nuts, washers including painting with two coat of red oxide, one coat of aluminum etc. for Double pole structure with RSJ/PSCC pole mentioned above item.	36511.00	AT Par	36511.00	
7	Please see Item Breakup for details. Description:- Supply, fabrication, galvanization and erection of steel gantries, portals, supporting structures, earth screen post structure and small parts steel work as per direction of site engineer.	40307.50	AT Par	40307.50	
8	Please see Item Breakup for details. Description:- Supply and stringing of 33 KV HT OH mains with ACSR 'Panther' conductor including binding and jumper connections etc.	9150.00	AT Par	9150.00	
9	Please see Item Breakup for details. Description:- Supply, erection, testing and commissioning of Aluminium tubular bus bar (Al-Alloy 63401 grade) nominal size 1-1/2" (outer dia- 48.26 mm, inside dia-40.89 mm, thickness 3.69 mm), medium gauge, length - 20 mtr, confirming to IS:5082 & IS:2673 with various bus bar connector complete with stainless steel nut, bolts, plan & spring washer and other requisite accessories	15880.00	AT Par	15880.00	
10	Please see Item Breakup for details. Description:- Supply and installation of 33KV Post type Insulators with all connected accessories.	6222.00	AT Par	6222.00	
	Please see Item Breakup for details.	136380.00	AT Par	136380.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

11	Description:- Supplying and erection of single piece nonlinear resistor type lightning arrestor suitable for 3 wire, 33 KV overhead lines with rated voltage 30 KV (rms) with a nominal discharge current rating of 10 KA (station class) and complete with galvanised clamping arrangement, G.I.bolts, nuts, washers etc. as required.			
12	Please see Item Breakup for details.	2832.00	AT Par	2832.00
	Description:- Supply, fitting, fixing of 33 KV 10 KN Pin Insulator (polymeric type) with 900 mm crepage distance including all hardware materials			
13	Please see Item Breakup for details.	4608.00	AT Par	4608.00
	Description:- Supply, fitting, fixing of 33 KV 70 KN Disc Insulator (polymeric type) including all hardware materials.			
14	Please see Item Breakup for details.	465480.00	AT Par	465480.00
	Description:- Supply, Installation, testing, commissioning of Current Transformer, 1-ph, 33 KV, 100 A, 25 KAWith 120% extendedcurrent rating, systemvoltage 36 KV.			
15	Please see Item Breakup for details.	341712.00	AT Par	341712.00
	Description:- Supply, Installation, testing,commissioning of 33 KV/110V, Potential transformer (1-ph.),system voltage 36 KV.			
16	Please see Item Breakup for details.	66480.00	AT Par	66480.00
	Description:- Supply & fabrication of steel structures for installation of CT, PT & VCBs as per details			
17	Please see Item Breakup for details.	15497294.00	AT Par	15497294.00
	Description:- Supply,installation,testing andcommissioning ofoutdoor 33/11 KV, 5 MVA (5000KVA), 50C/S, 3 phase, Oilimmersed, ONAN,Copper wounded, automatic on loadtap Changermotor operated 415 V, 50 Hz AC,17 tapings of 5% voltage on Higherside and variation+5% to -15% instep of 1.25%,outdoor type as per IS:2026 or latest with OLTC &RTCC, and with all connected accessories as per directions of Engineer at site.			
18	Please see Item Breakup for details.	105011.00	AT Par	105011.00
	Description:- Supply and installation of 3-PH 63 kVA 33 kV/433 V Distribution Transformer with BIS EE Level-3 as per uploaded specification. Makes:Mahindra/Servokon/Kirloskeronly			
19	Please see Item Breakup for details.	477074.00	AT Par	477074.00
	Description:- 1) SETC of 20 KVA Online UPS with isolation transformer for lighting load. Phase: 3PH-1PH Warranty: 2 Years from Supply - 01 Nos, 2) SETC of 100AH/12V Batteries for your 2 Hrs. battery backup proposed load. Make: Exide Warranty: 2 years from supply - 32 Nos, 3) SETC of Battery Rack & Link - 01 Nos, 4) transportation & Installation charges - 01 Nos.			
20	Please see Item Breakup for details.	54000.00	AT Par	54000.00
	Description:- Earth work in excavation as per the instructions of site engineer and dumping at embankment site or spoil heap,within railway land, including 50m lead and 1.5m lift, etc., -All kinds of soils			
21	Please see Item Breakup for details.	48500.00	AT Par	48500.00
	Description:- Supply, fabrication, fixing and erection of MS Work of miscellaneous size and for cable tray etc. including painting complete.			
22	Please see Item Breakup for details.	524400.00	AT Par	524400.00
	Description:- Supply of 3 core 120 mm ² 33 KV XLPE UG armored Aluminum Cable, confirming of IS7098 Pt.II /1985 or latest.			
23	Please see Item Breakup for details.	205260.00	AT Par	205260.00
	Description:- Supply and erection of 33 KV heat shrink cable straight through jointing kit upto 3 core 300Sq.mm.			
24	Please see Item Breakup for details.	228910.00	AT Par	228910.00
	Description:- Supply , installation,testing & commissioning of 33 KV Outdoor type heat shrinkable cable termination kit upto 3 core 300 Sq.mm.			
25	Please see Item Breakup for details.	570980.00	AT Par	570980.00
	Description:- Supply and making indoor cable end termination shrinkable jointing kit complete with all accessories including lugs with heat suitable for 120 sq.mm of 3 core, XLPE aluminium conductor cable for 33 KV grade as required.			
26	Please see Item Breakup for details.	723600.00	AT Par	723600.00
	Description:- Supply of cable 3 core 300Sq.mm XLPE insulated Al armored cable 11 KV grade.			
27	Please see Item Breakup for details.	177600.00	AT Par	177600.00
	Description:- Supply of 3 core 240 mm ² 11KV HT XLPE UG armored Aluminum Cable, confirming of IS 7098 Pt.II /1985 or latest.			
28	Please see Item Breakup for details.	142400.00	AT Par	142400.00
	Description:- Supply of 3 core 185 mm ² 11KV HT XLPE UG armored Aluminum Cable, confirming of IS 7098 Pt.II/1985 or latest.			
	Please see Item Breakup for details.	84550.00	AT Par	84550.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

29	Description:- Supply, fixing, connecting, testing & commissioning of outdoor type Heat shrinkable cable termination kit for outdoor type 11 KV 3 core 240-300 sq mm HT XLPE cable with all connected accessories confirming to IS 13573/1992 or latest as per the directions of Engineer at site. Make: Raychem/RPG/Denson only			
	Please see Item Breakup for details.	1035800.00	AT Par	1035800.00
30	Description:- Construction of Reinforced concrete (Cable duct with 1:2:4 RCC concrete) providing with angular frames and covers as per the directions of engineer at site.			
	Please see Item Breakup for details.	148600.00	AT Par	148600.00
31	Description:- Construction providing of Cable trench & covers with 1:2:4 RCC concrete as per the directions of engineer at site			
	Please see Item Breakup for details.	81600.00	AT Par	81600.00
32	Description:- Supply of 11kV 3 core 95 sqmm HT Aluminium armoured cable conforming to IS: 7098-Part 2 :2011			
	Please see Item Breakup for details.	154500.00	AT Par	154500.00
33	Description:- Supply of 11 kV 3 core 120 sqmm HT Aluminium armoured cable conforming to IS: 7098-Part 2 :2011			
	Please see Item Breakup for details.	276580.00	AT Par	276580.00
34	Description:- Supply, erection, testing and commissioning of 11 kV HT outdoor heat shrinkable cable jointing/ terminating Kit suitable for 3 core 70/95/120/185 Sq.mm Aluminium armoured XLPE cable.			
	Please see Item Breakup for details.	207620.00	AT Par	207620.00
35	Description:- Supply, erection, testing & commissioning of 11 KV HT Indoor type end termination kit suitable for HT XLPE Cable.			
	Please see Item Breakup for details.	50400.00	AT Par	50400.00
36	Description:- Excavation of cable trench 30 cm wide x 120 cm deep in all types of soils for laying of HT UG/XLPE cable as per Railway specification or as per the directions of the engineer at site.			
	Please see Item Breakup for details.	14450.00	AT Par	14450.00
37	Description:- Cutting of esphalted road/ concrete/ cement/under the track etc., and excavation of cable trench of wide 40cm x 120cm for laying of HT cable. After laying of cable the trench should be brought to its original position by providing tar/ concrete/ cement as per the site conditions and as per directions of Rly Engineer.			
	Please see Item Breakup for details.	28500.00	AT Par	28500.00
38	Description:- Transportation, Laying, Installation, terminating, testing and commissioning of LT/HT cable of sizes 10 sqmm to 400 sqmm in existing trench, pipe or on structure.			
	Please see Item Breakup for details.	3400.00	AT Par	3400.00
39	Description:- Erection, testing and commissioning of cables other than trench i.e. Wall/Truss including clamp, GI wire and hardware			
	Please see Item Breakup for details.	9292.00	AT Par	9292.00
40	Description:- Supply & laying of GI pipe Class B, ISI marked under road /Clamping with erecting pole or wall as per technical specification & drawing for passing cable.			
	Please see Item Breakup for details.	66200.00	AT Par	66200.00
41	Description:- Supply and laying of HDPE (High Density Polyethylene pipe) pipe of PE-80 Grade in PN- 4 outer dia of HDPE pipe 160mm (nearest 6" dia) and wall thickness minimum 6.2mm maximum 7.1mm with joints, bends, elbows etc. including all other connected accessories.			
	Please see Item Breakup for details.	45450.00	AT Par	45450.00
42	Description:- Supply and laying of HDPE pipe of PE-80 grade in PN-4 outer dia of HDPE pipe 110mm (nearest 4" dia) and wall thickness minimum 4.1 mm maximum 4.3 mm with 'T' joints, bends, elbows etc. including all other connected accessories.			
	Please see Item Breakup for details.	9300.00	AT Par	9300.00
43	Description:- Supply and laying of RCC half round pipe 150 mm ID & 1 mtr length.			
	Please see Item Breakup for details.	14140.00	AT Par	14140.00
44	Description:- Supply and laying of RCC Hume Pipe of size 6"(150mm) dia 2 mtr. Length.			
	Please see Item Breakup for details.	9980.00	AT Par	9980.00
45	Description:- Supply, erection of RCC Type cable route marker with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.			
	Please see Item Breakup for details.	8200.00	AT Par	8200.00
46	Description:- Supply, erection, testing & commissioning of RCC warning cover of size 18" X 7" X 1.5" in an approved manner			
	Please see Item Breakup for details.	229100.00	AT Par	229100.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

47	Description:- Construction of plinth for erecting the panel/DG set/VCB with stone / brick masonry with all connected accessories.				
	Please see Item Breakup for details.	157100.00	AT Par	157100.00	
48	Description:- Mass concreting of erected poles/ strut poles/ stays poles and stay sets with CC (1:3:6) using 40 mm size metal including the cost of metal, sand, cement and curring etc as per directions of site engineerand site condition.				
	Please see Item Breakup for details.	248400.00	AT Par	248400.00	
49	Description:- Supply and Spreading of 20 mm ballast in switch yard of different Sub-Station.				
	Please see Item Breakup for details.	360312.00	AT Par	360312.00	
50	Description:- Supply, erection, testing & commissioning of maintenance free earth as per RDSO specification no. RDSO/PE/SPEC/ PS/0109-008(REV '0') with improved earthing enhancing compound and exothermic welding				
	Please see Item Breakup for details.	18750.00	AT Par	18750.00	
51	Description:- Supply, laying,connecting &commissioning of 50x6 mm / 40x5 mm /25x6 mm thick GI Strip for earth pit as per the directions of engineer at site				
	Please see Item Breakup for details.	260620.00	AT Par	260620.00	
52	Description:- Supply and provision of earthing with copper earth plate 600mm x 600mm x3mm thickincluding accessories, and providing masonry enclosure with cover plate having lockingarrangement and water pipe of 2.7 meter long etc. with charcoal/coke and salt as required				
	Please see Item Breakup for details.	64400.00	AT Par	64400.00	
53	Description:- Supply and provision of 25mmx 5mm copper strip in 40mm dia G.I pipe from earthelectrode including connection with brass nut, bolt, spring, washer excavation and re-fillingetc. as required				
	Please see Item Breakup for details.	492758.00	AT Par	492758.00	
54	Description:- Provision and making of earth mesh 500 mm deep under the earth in 32x34 Sq.M area of switching yard as per RDSO drawing no. SKE 3975 attached including supplying and providing 35x6 mm copper strip at 3 mtr interval. Earthing the mat with copper plate size: 600 x600 x 6 mm (total 16 Nos.) 15' deep at each corner for connecting the equipment sand fencing including earth work, supply of copper plates, nuts, bolts and brazing of copper strip as required.				
	Please see Item Breakup for details.	187320.00	AT Par	187320.00	
55	Description:- Supply of earth pit materials and construction of earth pit as per IS 3043:1987 specification. This item also includes of supply and erection of CI pipe of size of 100mm inner diameter, 13mm thickness and 3000mm length. This work also includes of fabrication and fixing of GI strips for earthing connection. Excavated earth pit should be filled by mixture of coke/charcoal, salt and sand up to top. Provision of brick masonry chamber of size 650mmx650mm and depth up to 1000mm including light type CI cover frame and applying 12mm thick cement plaster in 1:3 inside and to all the exposed faces up to 300mm below. Foundation level, curing etc., All required materials for this job such as CI pipe cover with frame, salt, cement sand, charcoal gravel, bricks etc required bolts, nuts and double washers, number plates or painted plates. Tentative quantity of salt and charcoal shall be of 2.5CMt. The CI pipe should be painted with 2 coats of bitumen paint as per the directions of Rly engineer at site. Note: The work (Earthing arrangement with all accessories) should be strictly done as per IS 3043:1987 specification or latest.				
	Please see Item Breakup for details.	330105.00	AT Par	330105.00	
56	Description:- Fencing arrangements to the 33kV HT New sub station yard NOTE:- For the details under tender document and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(a) Supply and erection of Fencing Panels				
	Please see Item Breakup for details.	104013.00	AT Par	104013.00	
57	Description:- Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(b) Supply and erection of Fencing Uprights				
	Please see Item Breakup for details.	26134.00	AT Par	26134.00	
58	Description:- Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(c) Supply and erection of Anti climbing device				
	Please see Item Breakup for details.	23848.00	AT Par	23848.00	
59	Description:- Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(d) Foundation of upright Type-I				
	Please see Item Breakup for details.	17886.00	AT Par	17886.00	
60	Description:- Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(e) Foundation of upright Type-II				
	Please see Item Breakup for details.	34560.00	AT Par	34560.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

61	Description:- Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C/sheet No. 1 & 2 and ETI/PSI/104(f) Supply and erection of Gate with lock			
	Please see Item Breakup for details.	6764.00	AT Par	6764.00
62	Description:- Coping of poles stay poles /stays with a height of 470mm x450mm x450mm or suitable size withCC(1:3:6) using 20mm size metal including the cost of metal sand, cement and curring etc as perdirections of site engineer and site condition.			
	Please see Item Breakup for details.	84228.00	AT Par	84228.00
63	Description:- Supply of portable Fire Extinguishers dry chemical type 9/10 Kgs. Capacity fitted with gun metal cap.Dry chemical powder 9/10 Kgs conform to IS:4303 and carbondioxide conform to IS 4947.			
	Please see Item Breakup for details.	37630.00	AT Par	37630.00
64	Description:- Supply of Fire extinguisher 5 KG capacity Dry type.			
	Please see Item Breakup for details.	15174.00	AT Par	15174.00
65	Description:- Supply and Erection of Fire Bucket Stand with 4 Nos Bucket Each capacity 9 Ltr including Locking Arrangement.			
	Please see Item Breakup for details.	8715.00	AT Par	8715.00
66	Description:- Suuply and installation of Insulated Rubber Matting (33 KV & 11KV) non skid type with fluted type and plain border size 2 mtr X 1 mtr X 12 mm thick.			
	Please see Item Breakup for details.	33924.00	AT Par	33924.00
67	Description:- Supply of Tool Kit No. 1002 for Tube wells of size of Box 560x280x310mm with total no. of content of Tools chest 32 Nos (Bi hexagon ring spanner 21x23mm -2 No, Double open End spanner 6x7-20x22mm, 7/16x1/2ww-8No, Heavy duty pipe wrenches 350&450mm-2No, Grip lock plier 250mm-2No, Screw driver Engineer pattern 5x75 & 8x200mm-1No. Ball pein Hammer 500gms-2no,Adjustable wrench 300mm-1no, Bolt Die set 1/2"BSW-1no, Chain pipe vice 50mm-1no, Cold Chisel150mm-1no, Flat File 250mm with handle-1no, Hacksaw Frame 300mm-1no, Spirit Level 200mm-1no, Measuring Tape Steel 2Mtr-1no, Oil Can -1no, Pipe Clamp-1no, Die set 1.1/4-1.1/2 BSP-2no,Tommy Bar 460mm-1no, Wire Brush-1no, Tool Chest-1no. of M/s. Tappary/ Everest make only			
	Please see Item Breakup for details.	26215.00	AT Par	26215.00
68	Description:- Supply of Air velocity and Ambient temperature and Surface temperature and Humidity VaneAnemometer.			
	Please see Item Breakup for details.	7743.00	AT Par	7743.00
69	Description:- Supply of 33KV discharge rod of standard make withsuitable top and bottom copper clamps with connecting cables as approved by Rly. Authority			
	Please see Item Breakup for details.	10355.00	AT Par	10355.00
70	Description:- Supply of Fluke 362 Clamp Meter With Light			
	Please see Item Breakup for details.	7075.00	AT Par	7075.00
71	Description:- Supply of Digital Megger 500 V.			
	Please see Item Breakup for details.	14436.00	AT Par	14436.00
72	Description:- Supply of Digital Megger 2500 V.			
	Please see Item Breakup for details.	15000.00	AT Par	15000.00
73	Description:- Price for supply of hand drive nmetal body generator type insulation tester megger 5000 V / 20000 Mega ohms.			
	Please see Item Breakup for details.	52705.00	AT Par	52705.00
74	Description:- Supply of Digital Clamp on Earth Tester.			
	Please see Item Breakup for details.	8083.00	AT Par	8083.00
75	Description:- Supply of infrared Thermometer.			
	Please see Item Breakup for details.	27088.00	AT Par	27088.00
76	Description:- Supply and fixing of Surveillance security system with 4Pcs 5MP Full HD 8CH DVR Bullet Cameras, 2Pieces Dome Camera, 1TB Hard Disc, CCTV Wire Roll, Power Supply and All Required Connectors.Model No.Hikvision (DS-7208 HQHI-M1/S) /(DS-7B08HQHI-K1) 8CH DVR			
	Please see Item Breakup for details.	41634.00	AT Par	41634.00
77	Description:- Supply and fixing of Surveillance security system with 4Pcs 5MP Full HD 8CH DVR Bullet Cameras, 2Pieces Dome Camera, 1TB Hard Disc, CCTV Wire Roll, Power Supply and All Required Connectors.Model No.Hikvision (DS-7208 HQHI-M1/S) /(DS-7B08HQHI-K1) 8CH DVR			
	Please see Item Breakup for details.	13890.00	AT Par	13890.00
78	Description:- Supply of hp inkjet Colour Computer Printers for A4 paper size Brand: HP			
	Please see Item Breakup for details.	4025.00	AT Par	4025.00
79	Description:- Supply & erection of Danger Board for 33/11 KV system			
	Please see Item Breakup for details.	260.00	AT Par	260.00
80				

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

	Description:- Supply of Shock treatment boards.								
81	Please see Item Breakup for details.		779.00	AT Par	779.00				
	Description:- Supply & erection of Substation layout board made of GI sheet and rigid frame								
82	Please see Item Breakup for details.		33423.00	AT Par	33423.00				
	Description:- Survey, design and preparation of drawings of 33/11KV sub-station including over head line								
83	Please see Item Breakup for details.		13485.00	AT Par	13485.00				
	Description:- Supply and Erection of Sub station Name board including required fitting.								
84	Please see Item Breakup for details.		2647.00	AT Par	2647.00				
	Description:- Preparation of Substation Schematic Diagram on Auto Cad with one set of soft copy and 2 set of hard copy in hard glass frame for display in Sub-Station.								
85	Please see Item Breakup for details.		17712.00	AT Par	17712.00				
	Description:- Supply of Aluminium extension Ladder (light weight) 20' closed height and 30' extended height								
86	Please see Item Breakup for details.		5396.00	AT Par	5396.00				
	Description:- Supply of Aluminium Ladder 12' long (Platform type)								
87	Please see Item Breakup for details.		6909.00	AT Par	6909.00				
	Description:- Supply of Aluminium telescopic ladder, heavy duty with holding rubber, foldable with equal steps, 12 to 13 Feet height with push button type system ladder								
88	Please see Item Breakup for details.		6500.00	AT Par	6500.00				
	Description:- Supply of GREEN PANEL PLYWOOD 2400X1200 mm MR Plywood								
89	Please see Item Breakup for details.		1668.00	AT Par	1668.00				
	Description:- Supply of Safety Belt								
90	Please see Item Breakup for details.		3440.00	AT Par	3440.00				
	Description:- Supply of First Aid Box including medicines.								
91	Please see Item Breakup for details.		3400.00	AT Par	3400.00				
	Description:- Supply Rubber hand globes for 33KV (for both hands) .								
92	Please see Item Breakup for details.		26569.00	AT Par	26569.00				
	Description:- Supply of battery operated Saw cutting having Weight less than 5 Kg Complete.								
93	Please see Item Breakup for details.		7238.00	AT Par	7238.00				
	Description:- Supply of Heavy duty Hammer Drill Machine of approved make.								
94	Please see Item Breakup for details.		16509.00	AT Par	16509.00				
	Description:- Supply of Hydraulic crimping tools capacity 10 mm2 to 185 mm2 dies: R-1 to R13.								
95	Please see Item Breakup for details.		4506.00	AT Par	4506.00				
	Description:- Portable hand held electric air blower (Detail specification attached.) DEWALT Fibre Body Handheld Electric Blower, Warranty 12 months								
96	Please see Item Breakup for details.		6357.00	AT Par	6357.00				
	Description:- Long Range 1KM Torch Light Beam Battery Included 1500 Lumens.								
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit	
Schedule () I-(B) : Electrical Portion							1040154.00		
1	Please see Item Breakup for details.		31750.00	AT Par	31750.00				
	Description:- Wiring of the concealed Light / fan Point with all accessories and running earthing copper conductor as per standard practise. The switches shall be of modular type.(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site.)								
2	Please see Item Breakup for details.		7260.00	AT Par	7260.00				
	Description:- Supply of material and fixing and concealed wiring for (3 Plug & 3 switch on separate board) 6 A 3 pin universal socket outlet complete with 6 Sqmm PVC insulated copper conductor wires along with 14 SWG tinned copper earth wire in 25mm / 32mm dia PVC conduit pipe flush type 5A socket outlet and 5A piano type switch in GI box with PVC topsheet 5mm thick..(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)								
3	Please see Item Breakup for details.		6350.00	AT Par	6350.00				
	Description:- Supply, erection, testing & commissioning of 6A & 3 Pin Universal Modular Type Plug Socket with switch & concealed type point wiring with 2x2.5 sq mm FRLS Multistranded PVC Copper wire with all accessories and running earth on seprate board..(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)								

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

4	Please see Item Breakup for details.	11310.00	AT Par	11310.00	
	Description:- Wiring of Concealed 15 A 6 Pin Wall Socket Point complete with 4 Sqmm Wiring all accessories and running earthing copper conductor as per standard practice. The switches shall be of modular type for Gyser, Kettle & Fridge.(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)				
5	Please see Item Breakup for details.	4436.00	AT Par	4436.00	
	Description:- Supplying & erecting CRCA sheet metal enclosures of 1.2mm thickness with 20A, 2 pin plug & earth socket and 20A, 3 pin plug top with 20A/32A single pole MCB having rated short - circuit breaking capacity (Icn) 10kA complete erected on provided angle iron/GI frame.				
6	Please see Item Breakup for details.	9000.00	AT Par	9000.00	
	Description:- Supply, erection, testing & commissioning of Submain from switch board to single phase DP switch / DP one circuit meter comprising of 2x4 sq.mm. PVC insulated FRLS 1.1KV multistranded wire & one running earth of 2.5 sq.mm. copper conducting PVC insulation green colour of 1.1 KV grade on rigid PVC casing capping with all accessories.				
7	Please see Item Breakup for details.	11300.00	AT Par	11300.00	
	Description:- Supply, erection, testing & commissioning of Submain with 2x6 sqmm FRLS copper wire inside PVC Casing capping with running earth etc complete. (1 m length of submain consists one cktmtr including all accessories & 2 wire of 6 sqmm with one wire of 2.5 sqmm for earth conn).				
8	Please see Item Breakup for details.	9360.00	AT Par	9360.00	
	Description:- Supply, erection, testing & commissioning of energy efficient 1x18 W indoor fitting LED batten with extruded aluminium housing with integrated LED Driver/Tube complete and associated accessories complete.				
9	Please see Item Breakup for details.	79760.00	AT Par	79760.00	
	Description:- SETC of LED street Light Roadway fittings in aluminium PDC housing, toughened glass cover with IP66 protection, Wattage-72 watts, input voltage-240 volts ac, 50Hz. Complete with PIR sensor based with Auto dimming facility.				
10	Please see Item Breakup for details.	96380.00	AT Par	96380.00	
	Description:- LED Flood light fittings of 250watt with IP 66 protection and 5 years warranty as per attached GEM specification.Required make- Halonix or similar. 250W LED Luminaire for flood light Brand:OREVA Category Name & Quadrant: Led Luminaire (for flood Light) IS 10322 IS:16107 (Q3) & 250 WATT IP 66 Flood Light with 5 Year warranty				
11	Please see Item Breakup for details.	12490.00	AT Par	12490.00	
	Description:- Supply, erection, testing & commissioning of Lighting Circuit Board, Double Door Powder coated with locking arrangement consisting 32 A DP ELCB/RCBO as I/C and 6 Nos x 6 A SPMCB and 2 Nos x 20A O/G SPMCB Complete.				
12	Please see Item Breakup for details.	152740.00	AT Par	152740.00	
	Description:- Supply, erection, testing & commissioning of 7 Mtr high (clear height) galvanised octagonal pole with foundation bolts having bottom of 130 mm A/F, top 70 mm A/F on provided foundation.(Along with 2 pole RCBO 6A, with 30 mA sensitivity).				
13	Please see Item Breakup for details.	6306.00	AT Par	6306.00	
	Description:- Providing & erecting epoxy outdoor / indoor end termination kit for LT XLPE armoured cable 2.5 to 16 sq mm., with necessary material as per specification				
14	Please see Item Breakup for details.	5090.00	AT Par	5090.00	
	Description:- Providing & erecting epoxy outdoor / indoor end termination kit for LT XLPE armoured cable 25 to 50 sq mm., with necessary material as per specification				
15	Please see Item Breakup for details.	33054.00	AT Par	33054.00	
	Description:- Supply, erection, testing & commissioning of Astronomical Timer 3Ph with multitiming setting including suitable contactor of 100 Amp.				
16	Please see Item Breakup for details.	13182.00	AT Par	13182.00	
	Description:- Supply, fixing, testing & commissioning of energy efficient BLDC motor industrial exhaust fan of size 300 mm (12") sweep and standard accessories, as per specifications in Annexure II. (Minimum Warrantee - 2 years)				
17	Please see Item Breakup for details.	27430.00	AT Par	27430.00	
	Description:- Supply & fixing of 1200 mm sweep energy saving BLDC ceiling fan with Remote, 300mm length of down rod (without shackle), input power not more than 28W, minimum 1.1mm aluminum blade material, double ball bearing, 2 canopy, to be operated in AC single phase supply. as per specification.				
18	Please see Item Breakup for details.	30026.00	AT Par	30026.00	
	Description:- Supply, erection, testing & commissioning of maintenance free earth as per RDSO specification no. RDSO/PE/SPEC/ PS/0109-008(REV '0') with improved earthing enhancing compound and exothermic welding				
	Please see Item Breakup for details.	3750.00	AT Par	3750.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

19	Description:- Supply, laying,connecting &commissioning of 50x6 mm / 40x5 mm /25x6 mm thick GI Strip for earth pit as per the directions of engineer at site							
20	Please see Item Breakup for details.		37600.00		AT Par		37600.00	
	Description:- SETC of 2 core 10 sqmm Armoured Aluminium Cable with continuous GI earth wire complete erected with glands and lugs on wall/truss etc.							
21	Please see Item Breakup for details.		46400.00		AT Par		46400.00	
	Description:- Supply of 4 core 25 sqmm armoured XLPE Cable.							
22	Please see Item Breakup for details.		79600.00		AT Par		79600.00	
	Description:- Supply of LT XLPE Armoured 4 Core 50 Sqmm Aluminium cable as per relevant IS.							
23	Please see Item Breakup for details.		41400.00		AT Par		41400.00	
	Description:- Trenching & refilling of LT/HT/ Various sizes of PVC / XLPE cables- Along the Road (Size - 900mm x 300mm)							
24	Please see Item Breakup for details.		36800.00		AT Par		36800.00	
	Description:- Digging of cable trench 300/450 mm x 1000 mm in RCC/PCC/hard soil & refilling as per specification and requirement at the site.							
25	Please see Item Breakup for details.		9000.00		AT Par		9000.00	
	Description:- Transportation, Laying, Installation, terminating, testing and commissioning of LT/HT cable of sizes 10 sqmm to 400 sqmm in existing trench, pipe or on structure.							
26	Please see Item Breakup for details.		6800.00		AT Par		6800.00	
	Description:- Erection,testing and commissioning of cables other than trench i.e.Wall/Truss including clamp, GI wire and hardware							
27	Please see Item Breakup for details.		2020.00		AT Par		2020.00	
	Description:- Supply & laying of GI pipe Class B, ISI marked under road /Clamping with erecting pole or wall as per technical specification & drawing for passing cable.							
28	Please see Item Breakup for details.		9300.00		AT Par		9300.00	
	Description:- Supply and laying of RCC half round pipe 150 mm ID & 1 mtr length.							
29	Please see Item Breakup for details.		1414.00		AT Par		1414.00	
	Description:- Supply and laying of RCC Hume Pipe of size 6"(150mm) dia 2 mtr. Length.							
30	Please see Item Breakup for details.		4990.00		AT Par		4990.00	
	Description:- Supply, erection of RCC Type cable route marker with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.							
31	Please see Item Breakup for details.		4230.00		AT Par		4230.00	
	Description:- Supply & Erection of RCC Warning Cover and refilling the cable trench in an approved manner.							
32	Please see Item Breakup for details.		24500.00		AT Par		24500.00	
	Description:- "Supply, installation and commissioning of RO water purifier with pre filter. Capacity: 50 LPH. Specification as decribed.Also Fully automatic with auto cut off RO+UV+UF Potable Water Purification System "							
33	Please see Item Breakup for details.		9291.00		AT Par		9291.00	
	Description:- Supply of Steel Almirah, Size - 6 ft x 3 ft							
34	Please see Item Breakup for details.		32685.00		AT Par		32685.00	
	Description:- Table for operator similar to Godrej Model							
35	Please see Item Breakup for details.		65370.00		AT Par		65370.00	
	Description:- Chair for operator similar to Godrej Model							
36	Please see Item Breakup for details.		28307.00		AT Par		28307.00	
	Description:- Supply of tool storage box Dimensions WxHxD(cm) 91.6x198x48 for kept sub station tools. GodrejProduct ID:30161803SD00206							
37	Please see Item Breakup for details.		40234.00		AT Par		40234.00	
	Description:- Supply of L Shape test bench Wooden and Metal Godrej Maestro Desk for for sub station instrumenttest bench with 4 nos modular type 6/16A socket wiring arrangemnts.							
38	Please see Item Breakup for details.		9239.00		AT Par		9239.00	
	Description:- Supply and installation of Chairs revolving type for work station as per specification							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 33 KV FEEDER BAY With Gantry structure & PT							864147.98	
1	Please see Item Breakup for details.		18898.47		AT Par		18898.47	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

	Description:- 33 KV Lightning Arrestors (Station type)							
2	Please see Item Breakup for details.			86158.82	AT Par	86158.82		
	Description:- 33 KV Isolators with EB (800 A)							
3	Please see Item Breakup for details.			157707.36	AT Par	157707.36		
	Description:- 33 KV Isolators without EB (800 Amp.)							
4	Please see Item Breakup for details.			307129.52	AT Par	307129.52		
	Description:- 33 KV VCB complete 1600 Amp (O.D.)							
5	Please see Item Breakup for details.			92612.76	AT Par	92612.76		
	Description:- 33 KV P.T.							
6	Please see Item Breakup for details.			114580.23	AT Par	114580.23		
	Description:- CT 200-100/1-1 A , 33 KV							
7	Please see Item Breakup for details.			79895.68	AT Par	79895.68		
	Description:- C&R panel for 33 KV for feeder breaker							
8	Please see Item Breakup for details.			7165.14	AT Par	7165.14		
	Description:- Marshalling Box							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 9-a) Structure							232684.20	
1	Please see Item Breakup for details.			21682.50	AT Par	21682.50		
	Description:- Structure for 33 KV L.A.							
2	Please see Item Breakup for details.			27319.95	AT Par	27319.95		
	Description:- Structure for 33 KV CT							
3	Please see Item Breakup for details.			27319.95	AT Par	27319.95		
	Description:- Structure for 33 KV PT							
4	Please see Item Breakup for details.			117705.00	AT Par	117705.00		
	Description:- G.I. Gantry Structures							
5	Please see Item Breakup for details.			13876.80	AT Par	13876.80		
	Description:- G.I.Nut Bolts							
6	Please see Item Breakup for details.			24780.00	AT Par	24780.00		
	Description:- Welding Rods							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 9-b) Foundation (Civil works)							85096.55	
1	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Isolators with EB							
2	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Isolators without EB							
3	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV C.Ts							
4	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV P.Ts							
5	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Lightning Arrestor							
6	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Breaker							
7	Please see Item Breakup for details.			21274.13	AT Par	21274.13		
	Description:- Foundation for Gantry Structures							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 9-c) Bus-Bar Material							199699.40	
1	Please see Item Breakup for details.			5018.00	AT Par	5018.00		
	Description:- AAAC 232 mm2							
2	Please see Item Breakup for details.			143290.20	AT Par	143290.20		
	Description:- Wedge Connectors : T-Connector for 200 sq mm conductor(Compression type)							

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

3	Please see Item Breakup for details.				14429.40	AT Par	14429.40	
	Description:- Breaker Clamps							
4	Please see Item Breakup for details.				14451.72	AT Par	14451.72	
	Description:- clamps for Isolator							
5	Please see Item Breakup for details.				10087.92	AT Par	10087.92	
	Description:- Clamps for CTs							
6	Please see Item Breakup for details.				7270.38	AT Par	7270.38	
	Description:- Disc Insulator 11 KV 70 KN							
7	Please see Item Breakup for details.				5151.78	AT Par	5151.78	
	Description:- Strain Hardware for AAAC232 sq.mm.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 9-d) Control Cable							64084.10	
1	Please see Item Breakup for details.				29364.50	AT Par	29364.50	
	Description:- Armoured Copper control cable 19C X 2.5 Sq mm							
2	Please see Item Breakup for details.				3915.20	AT Par	3915.20	
	Description:- Armoured Copper control cable 2Cx2.5 sq.mm.							
3	Please see Item Breakup for details.				6628.50	AT Par	6628.50	
	Description:- Armoured Copper control cable 2Cx4 sq.mm.							
4	Please see Item Breakup for details.				4745.40	AT Par	4745.40	
	Description:- Cable Trays 2.5 Mtr. X 6" W							
5	Please see Item Breakup for details.				746.62	AT Par	746.62	
	Description:- Cable Glands, rerules and tape etc.							
6	Please see Item Breakup for details.				1734.60	AT Par	1734.60	
	Description:- Angle for fixing trays 50x50x6mm							
7	Please see Item Breakup for details.				15561.60	AT Par	15561.60	
	Description:- Half round cement pipe (150mm X 1mtr)							
8	Please see Item Breakup for details.				1387.68	AT Par	1387.68	
	Description:- Sand							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 9-e) Painting of Structure							3147.10	
1	Please see Item Breakup for details.				1536.40	AT Par	1536.40	
	Description:- Red Oxide Paint for 2 coats							
2	Please see Item Breakup for details.				1610.70	AT Par	1610.70	
	Description:- Aluminium Paint for 1 coat							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-A-I : 10) Earthing work							21425.05	
1	Please see Item Breakup for details.				4027.00	AT Par	4027.00	
	Description:- M.S. Flats(50 X 10mm)							
2	Please see Item Breakup for details.				1610.80	AT Par	1610.80	
	Description:- M.S.Flat 25x6 mm							
3	Please see Item Breakup for details.				9112.85	AT Par	9112.85	
	Description:- Earthing Sets H.T of C.I.pipe 150 mm 3 mtr.							
4	Please see Item Breakup for details.				2106.00	AT Par	2106.00	
	Description:- Coal							
5	Please see Item Breakup for details.				1486.80	AT Par	1486.80	
	Description:- Salt							
6	Please see Item Breakup for details.				248.00	AT Par	248.00	
	Description:- Welding Rods							
7	Please see Item Breakup for details.				339.49	AT Par	339.49	
	Description:- Hiring of Welding machine							
8	Please see Item Breakup for details.				2494.11	AT Par	2494.11	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Description:- Brick & Masonary works for earthing pit								
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-B-I : Cost Data for laying of 33 KV 3 C 300 mm 2 XLPE under ground Cable for 4 nos locations at Tower Line/Road/Alongwith Railway Line: 2.376 Km (With Standby)							8278367.31	
1	Please see Item Breakup for details.				7025601.53	AT Par	7025601.53	
	Description:- XLPE Cable 33 KV, 3 C / 300 mm sq.							
2	Please see Item Breakup for details.				42677.50	AT Par	42677.50	
	Description:- R.C.C. Pipe 150 mm 2 M							
3	Please see Item Breakup for details.				409238.63	AT Par	409238.63	
	Description:- RCC Tiles (0.6 x 0.5) Mtrs.							
4	Please see Item Breakup for details.				104152.46	AT Par	104152.46	
	Description:- 33 kV Heat shrink Straight through joint (AI) kit for XLPE 3 C X 300 sqmm							
5	Please see Item Breakup for details.				429658.72	AT Par	429658.72	
	Description:- 33 kV Heat shrink Outdoor termination joint (AI) kit for XLPE 3 C X 300 sqmm							
6	Please see Item Breakup for details.				94230.08	AT Par	94230.08	
	Description:- Sand							
7	Please see Item Breakup for details.				68392.80	AT Par	68392.80	
	Description:- HDPE/GI Pipe							
8	Please see Item Breakup for details.				20061.76	AT Par	20061.76	
	Description:- Earthing Sets H.T							
9	Please see Item Breakup for details.				82793.28	AT Par	82793.28	
	Description:- 33 KV Lightning Arrestors (Station type)							
10	Please see Item Breakup for details.				1560.55	AT Par	1560.55	
	Description:- Misc. for XLPE U/G Cable							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-C-I : LAYING OF 33 KV UNDER GROUND CABLE FOR Railway Crossing One+One (Spare) Cable - 3 Locations Total: 2*304=608 Rmt							2519573.17	
1	Please see Item Breakup for details.				1797797.02	AT Par	1797797.02	
	Description:- XLPE Cable 33 KV, 3 C / 300 mm sq.							
2	Please see Item Breakup for details.				233675.40	AT Par	233675.40	
	Description:- HDPE/GI Pipe							
3	Please see Item Breakup for details.				15681.60	AT Par	15681.60	
	Description:- G. I. Pipe 110 mm							
4	Please see Item Breakup for details.				3761.58	AT Par	3761.58	
	Description:- HT Earthing For Cable							
5	Please see Item Breakup for details.				322244.04	AT Par	322244.04	
	Description:- 33 kV Heat shrink Outdoor termination joint (AI) kit for XLPE 3 C X 300 sqmm							
6	Please see Item Breakup for details.				17098.20	AT Par	17098.20	
	Description:- Sand							
7	Please see Item Breakup for details.				8549.10	AT Par	8549.10	
	Description:- Misc. For XLPE U/G Cable							
8	Please see Item Breakup for details.				47976.75	AT Par	47976.75	
	Description:- 33 KV LA 9 KA							
9	Please see Item Breakup for details.				72789.48	AT Par	72789.48	
	Description:- RCC Tiles (0.6 x 0.5) Mtrs.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-D-I : 33 KV S/C Line Suspension type with 100 mm ² AAAC lines on 152 X 152 mm 13 mtr. RSJ: 5.4 Km.							5926831.00	
1	Please see Item Breakup for details.				2172550.05	AT Par	2172550.05	
	Description:- RSJ 152x152, 13 m long							
2	Please see Item Breakup for details.				248656.68	AT Par	248656.68	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

	Description:- RSJ 116x100, 11 m long (For Stud)								
3	Please see Item Breakup for details.		253908.27		AT Par	253908.27			
	Description:- MS Channel 100x50x6 mm								
4	Please see Item Breakup for details.		46735.08		AT Par	46735.08			
	Description:- M.S.Channel 75x40x6 mm								
5	Please see Item Breakup for details.		104489.00		AT Par	104489.00			
	Description:- MS angle 50x50x6 mm								
6	Please see Item Breakup for details.		42652.80		AT Par	42652.80			
	Description:- MS Flat 75x10 mm								
7	Please see Item Breakup for details.		65655.36		AT Par	65655.36			
	Description:- G.I.Nut Bolts								
8	Please see Item Breakup for details.		282682.10		AT Par	282682.10			
	Description:- Disc Insulator 11 KV 70 KN								
9	Please see Item Breakup for details.		40962.87		AT Par	40962.87			
	Description:- SSN Hardware for 0.1 Dog or AAAC 100 Sq.mm								
10	Please see Item Breakup for details.		48200.64		AT Par	48200.64			
	Description:- Strain Hardware for Dog0.1 or Equ.AAAC.								
11	Please see Item Breakup for details.		1615779.90		AT Par	1615779.90			
	Description:- AAAC 100 mm2								
12	Please see Item Breakup for details.		35056.00		AT Par	35056.00			
	Description:- H.T.Stay Set								
13	Please see Item Breakup for details.		31265.28		AT Par	31265.28			
	Description:- G.I.Stay Wire 7/4mm(8 SWG)								
14	Please see Item Breakup for details.		68588.21		AT Par	68588.21			
	Description:- G.I.Wire 8 SWG/ 6 SWG								
15	Please see Item Breakup for details.		3408.80		AT Par	3408.80			
	Description:- Sleeve Joints								
16	Please see Item Breakup for details.		6493.30		AT Par	6493.30			
	Description:- Danger Board in yard.								
17	Please see Item Breakup for details.		34481.15		AT Par	34481.15			
	Description:- Earthing Sets H.T								
18	Please see Item Breakup for details.		644866.38		AT Par	644866.38			
	Description:- Concreting ration 1:3:6								
19	Please see Item Breakup for details.		35322.48		AT Par	35322.48			
	Description:- G.I.Barbed Wire 'A' type.								
20	Please see Item Breakup for details.		6595.02		AT Par	6595.02			
	Description:- Black bituminus paint								
21	Please see Item Breakup for details.		18173.16		AT Par	18173.16			
	Description:- Red Oxide Paint for 2 coats								
22	Please see Item Breakup for details.		17147.05		AT Par	17147.05			
	Description:- Aluminium Paint for 1 coat								
23	Please see Item Breakup for details.		19477.26		AT Par	19477.26			
	Description:- Sundries								
24	Please see Item Breakup for details.		83684.16		AT Par	83684.16			
	Description:- Wedge connectors :DOG TO DOG or equivalent AAAC								
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit	
Schedule () II-E-I : DOUPLE POLE STRUCTURE(cut point) OF- 33 KV LINE USING13 M LONG RSJ POLE with 33 KV Isolators with EB (800 A)							4496327.12		
1	Please see Item Breakup for details.		1896043.68		AT Par	1896043.68			
	Description:- RSJ 152x152, 13 m long								
2	Please see Item Breakup for details.		663084.48		AT Par	663084.48			
	Description:- RSJ 116x100, 11 m long (For Stud)								
3	Please see Item Breakup for details.		21326.40		AT Par	21326.40			
	Description:- M.S. Flats(50 X 10mm)								

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

4	Please see Item Breakup for details.				104868.96	AT Par	104868.96	
	Description:- MS Channel 100x50x6 mm							
5	Please see Item Breakup for details.				113988.00	AT Par	113988.00	
	Description:- MS angle 50x50x6 mm							
6	Please see Item Breakup for details.				182380.80	AT Par	182380.80	
	Description:- 33 kv guarding channel MS100x50							
7	Please see Item Breakup for details.				45187.92	AT Par	45187.92	
	Description:- 33 kV Pin Insulators with G.I. Pins							
8	Please see Item Breakup for details.				72300.96	AT Par	72300.96	
	Description:- Strain Hardware for Dog0.1 or Equ.AAAC.							
9	Please see Item Breakup for details.				191108.16	AT Par	191108.16	
	Description:- Disc Insulator 11 KV 70 KN							
10	Please see Item Breakup for details.				70112.00	AT Par	70112.00	
	Description:- H.T.Stay Set							
11	Please see Item Breakup for details.				62530.56	AT Par	62530.56	
	Description:- G.I.Stay Wire 7/4mm(8 SWG)							
12	Please see Item Breakup for details.				30092.64	AT Par	30092.64	
	Description:- Earthing Sets H.T							
13	Please see Item Breakup for details.				14069.38	AT Par	14069.38	
	Description:- G.I.Wire 8 SWG/ 6 SWG							
14	Please see Item Breakup for details.				18315.36	AT Par	18315.36	
	Description:- G.I.Barbed Wire 'A' type.							
15	Please see Item Breakup for details.				5666.88	AT Par	5666.88	
	Description:- Danger Board in yard.							
16	Please see Item Breakup for details.				4885.20	AT Par	4885.20	
	Description:- Black Bituminus Paint							
17	Please see Item Breakup for details.				12115.44	AT Par	12115.44	
	Description:- Red Oxide Paint for 2 coats							
18	Please see Item Breakup for details.				16935.36	AT Par	16935.36	
	Description:- Aluminium Paint for 1 coat							
19	Please see Item Breakup for details.				281908.80	AT Par	281908.80	
	Description:- Concreting ration 1:3:6							
20	Please see Item Breakup for details.				660550.94	AT Par	660550.94	
	Description:- 33 KV Isolators with EB (800 A)							
21	Please see Item Breakup for details.				28855.20	AT Par	28855.20	
	Description:- Sundries							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-F-I : Meter cubical for check & Main Meter							3121722.76	
1	Please see Item Breakup for details.				709656.72	AT Par	709656.72	
	Description:- XLPE Cable 33 KV, 3C/300 mm sq.							
2	Please see Item Breakup for details.				119497.42	AT Par	119497.42	
	Description:- Half round cement pipe (150mm X 1mtr)							
3	Please see Item Breakup for details.				84112.29	AT Par	84112.29	
	Description:- RCC Tiles (0.6 x 0.5) Mtrs.							
4	Please see Item Breakup for details.				429658.72	AT Par	429658.72	
	Description:- 33 kV Heat shrink Outdoor termination joint (AI) kit for XLPE 3 C X 300 sqmm							
5	Please see Item Breakup for details.				1031320.00	AT Par	1031320.00	
	Description:- 33 KV Metering Cubicle with metering CTs: Single Core Single Ratio: 100/5A, Class of Accuracy: 0.2s, Burden: 10VA, Confirming to IS-16227(Part I&II) suitable for 33 KV, MSEDCL Approved b) PTs: Single Core Single Ratio: 33KV/3/110V/3, Class of Accuracy: 0.2, Burden: 50VA, Confirming to IS-16227(Part I&II) suitable for 33 KV, MSEDCL Approved at Consumer End AND At both Source end i.e. at 132/33 KV Deepnagar SS and 33/11 KV Tapi nagar SS at C&R Panel, the HT TOD KVAH compatible Meters(Lead+Lag), Catagiry-C1,15 Minute DIP is proposed							
6	Please see Item Breakup for details.				191907.00	AT Par	191907.00	
	Description:- 33 KV LA 9 KA							

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

7	Please see Item Breakup for details.				6181.45	AT Par	6181.45	
	Description:- Foundation for L.A.							
8	Please see Item Breakup for details.				94990.00	AT Par	94990.00	
	Description:- Structure for L.A.							
9	Please see Item Breakup for details.				27140.00	AT Par	27140.00	
	Description:- Misc. Material							
10	Please see Item Breakup for details.				227650.32	AT Par	227650.32	
	Description:- Copper flat 25 x3 mm for earthing							
11	Please see Item Breakup for details.				113825.16	AT Par	113825.16	
	Description:- Copper Plate 4 mm thickness for earthing							
12	Please see Item Breakup for details.				21323.88	AT Par	21323.88	
	Description:- Earthing GI Pipes HT (One complete earthing for LA)							
13	Please see Item Breakup for details.				7303.32	AT Par	7303.32	
	Description:- Bentonite Clay							
14	Please see Item Breakup for details.				33707.52	AT Par	33707.52	
	Description:- Charcol Powder							
15	Please see Item Breakup for details.				23448.96	AT Par	23448.96	
	Description:- Raw Salt							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () II-G-I : Supply & fixing of AMR Modem							10812.00	
1	Please see Item Breakup for details.				10812.00	AT Par	10812.00	
	Description:- Supply & Fixing of Modem along with hardware accessories such as antenna, connectors, RS232 cable for connecting modem to meter.Configuration of Modem, Insertion of SIMcard & Confirmation of connectivity between MSEDCL MDAS & AMR end point, complete meter data availability in MSEDCL MDAS through Modem.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-A-II : 33 KV FEEDER BAY With Gantry structure & PT							864147.98	
1	Please see Item Breakup for details.				18898.47	AT Par	18898.47	
	Description:- 33 KV Lightning Arrestors (Station type)							
2	Please see Item Breakup for details.				86158.82	AT Par	86158.82	
	Description:- 33 KV Isolators with EB (800 A)							
3	Please see Item Breakup for details.				157707.36	AT Par	157707.36	
	Description:- 33 KV Isolators without EB (800 Amp.)							
4	Please see Item Breakup for details.				307129.52	AT Par	307129.52	
	Description:- 33 KV VCB complete 1600 Amp (O.D.)							
5	Please see Item Breakup for details.				92612.76	AT Par	92612.76	
	Description:- 33 KV P.T.							
6	Please see Item Breakup for details.				114580.23	AT Par	114580.23	
	Description:- CT 200-100/1-1 A , 33 KV							
7	Please see Item Breakup for details.				79895.68	AT Par	79895.68	
	Description:- C&R panel for 33 KV for feeder breaker							
8	Please see Item Breakup for details.				7165.14	AT Par	7165.14	
	Description:- Marshalling Box							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-A-II-9-a : STRUCTURE							232684.20	
1	Please see Item Breakup for details.				21682.50	AT Par	21682.50	
	Description:- Structure for 33 KV L.A.							
2	Please see Item Breakup for details.				27319.95	AT Par	27319.95	
	Description:- Structure for 33 KV CT							
3	Please see Item Breakup for details.				27319.95	AT Par	27319.95	
	Description:- Structure for 33 KV PT							
4	Please see Item Breakup for details.				117705.00	AT Par	117705.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

	Description:- G.I. Gantry Structures							
5	Please see Item Breakup for details.			13876.80	AT Par	13876.80		
	Description:- G.I.Nut Bolts							
6	Please see Item Breakup for details.			24780.00	AT Par	24780.00		
	Description:- Welding Rods							
S.No.							Item Code	Item Qty
							Qty Unit	Unit Rate
							Basic Value	Escl.(%)
							Amount	Bidding Unit
Schedule () III-A-II-9-b : FOUNDATION(Civil works)							85096.55	
1	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Isolators with EB							
2	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Isolators without EB							
3	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV C.Ts							
4	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV P.Ts							
5	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Lightning Arrestor							
6	Please see Item Breakup for details.			10637.07	AT Par	10637.07		
	Description:- Foundation for 33 kV Breaker							
7	Please see Item Breakup for details.			21274.13	AT Par	21274.13		
	Description:- Foundation for Gantry Structures							
S.No.							Item Code	Item Qty
							Qty Unit	Unit Rate
							Basic Value	Escl.(%)
							Amount	Bidding Unit
Schedule () III-A-II-9-c : BUS-BAR MATERIAL							199699.40	
1	Please see Item Breakup for details.			5018.00	AT Par	5018.00		
	Description:- AAAC 232 mm2							
2	Please see Item Breakup for details.			143290.20	AT Par	143290.20		
	Description:- Wedge Connectors : T-Connector for 200 sq mm conductor(Compression type)							
3	Please see Item Breakup for details.			14429.40	AT Par	14429.40		
	Description:- Breaker Clamps							
4	Please see Item Breakup for details.			14451.72	AT Par	14451.72		
	Description:- clamps for Isolator							
5	Please see Item Breakup for details.			10087.92	AT Par	10087.92		
	Description:- Clamps for CTs							
6	Please see Item Breakup for details.			7270.38	AT Par	7270.38		
	Description:- Disc Insulator 11 KV 70 KN							
7	Please see Item Breakup for details.			5151.78	AT Par	5151.78		
	Description:- Strain Hardware for AAAC232 sq.mm.							
S.No.							Item Code	Item Qty
							Qty Unit	Unit Rate
							Basic Value	Escl.(%)
							Amount	Bidding Unit
Schedule () III-A-II-9-d : CONTROL CABLE							64084.10	
1	Please see Item Breakup for details.			29364.50	AT Par	29364.50		
	Description:- Armoured Copper control cable 19C X 2.5 Sq mm							
2	Please see Item Breakup for details.			3915.20	AT Par	3915.20		
	Description:- Armoured Copper control cable 2Cx2.5 sq.mm.							
3	Please see Item Breakup for details.			6628.50	AT Par	6628.50		
	Description:- Armoured Copper control cable 2Cx4 sq.mm.							
4	Please see Item Breakup for details.			4745.40	AT Par	4745.40		
	Description:- Cable Trays 2.5 Mtr. X 6" W							
5	Please see Item Breakup for details.			746.62	AT Par	746.62		
	Description:- Cable Glands, rerules and tape etc.							
6	Please see Item Breakup for details.			1734.60	AT Par	1734.60		
	Description:- Angle for fixing trays 50x50x6mm							

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

7	Please see Item Breakup for details.				15561.60	AT Par	15561.60	
	Description:- Half round cement pipe (150mm X 1mtr)							
8	Please see Item Breakup for details.				1387.68	AT Par	1387.68	
	Description:- Sand							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-A-II-9-e : PAINTING OF STRUCTURE							3147.10	
1	Please see Item Breakup for details.				1536.40	AT Par	1536.40	
	Description:- Red Oxide Paint for 2 coats							
2	Please see Item Breakup for details.				1610.70	AT Par	1610.70	
	Description:- Aluminium Paint for 1 coat							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-A-II-10 : EARTHING WORK							21425.05	
1	Please see Item Breakup for details.				4027.00	AT Par	4027.00	
	Description:- M.S. Flats(50 X 10mm)							
2	Please see Item Breakup for details.				1610.80	AT Par	1610.80	
	Description:- M.S.Flat 25x6 mm							
3	Please see Item Breakup for details.				9112.85	AT Par	9112.85	
	Description:- Earthing Sets H.T of C.I.pipe 150 mm 3 mtr.							
4	Please see Item Breakup for details.				2106.00	AT Par	2106.00	
	Description:- Coal							
5	Please see Item Breakup for details.				1486.80	AT Par	1486.80	
	Description:- Salt							
6	Please see Item Breakup for details.				248.00	AT Par	248.00	
	Description:- Welding Rods							
7	Please see Item Breakup for details.				339.49	AT Par	339.49	
	Description:- Hiring of Welding machine							
8	Please see Item Breakup for details.				2494.11	AT Par	2494.11	
	Description:- Brick & Masonary works for earthing pit							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-B-II : Laying of 1 Km. 33 KV 3 C 300 mm 2 XLPE under ground Cable for 4 nos locations at Tower Line/Road/Along with Railway Line: 2.376 Km (With Standby)							4059814.09	
1	Please see Item Breakup for details.				2956903.00	AT Par	2956903.00	
	Description:- XLPE Cable 33 KV, 3 C / 300 mm sq.							
2	Please see Item Breakup for details.				25606.50	AT Par	25606.50	
	Description:- R.C.C. Pipe 150 mm 2 M							
3	Please see Item Breakup for details.				190061.42	AT Par	190061.42	
	Description:- RCC Tiles (0.6 x 0.5) Mtrs.							
4	Please see Item Breakup for details.				104152.46	AT Par	104152.46	
	Description:- 33 kV Heat shrink Straight through joint (AI) kit for XLPE 3 C X 300 sqmm							
5	Please see Item Breakup for details.				429658.72	AT Par	429658.72	
	Description:- 33 kV Heat shrink Outdoor termination joint (AI) kit for XLPE 3 C X 300 sqmm							
6	Please see Item Breakup for details.				94990.00	AT Par	94990.00	
	Description:- Sand							
7	Please see Item Breakup for details.				233675.40	AT Par	233675.40	
	Description:- HDPE/GI Pipe							
8	Please see Item Breakup for details.				2507.72	AT Par	2507.72	
	Description:- Earthing Sets H.T							
9	Please see Item Breakup for details.				20698.32	AT Par	20698.32	
	Description:- 33 KV Lightning Arrestors (Station type)							
10	Please see Item Breakup for details.				1560.55	AT Par	1560.55	
	Description:- Misc. for XLPE U/G Cable							

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () III-C-II : Cost data for 33 KV S/C Line Suspension type with 100 mm² AAAC lines on 152 X 152 mm 13 mtr. RSJ: 6.6 Km.							6089896.81	
1	Please see Item Breakup for details.				2607060.06	AT Par	2607060.06	
	Description:- RSJ 152x152, 13 m long							
2	Please see Item Breakup for details.				186492.51	AT Par	186492.51	
	Description:- RSJ 116x100, 11 m long (For Stud)							
3	Please see Item Breakup for details.				221706.66	AT Par	221706.66	
	Description:- MS Channel 100x50x6 mm							
4	Please see Item Breakup for details.				40750.71	AT Par	40750.71	
	Description:- M.S.Channel 75x40x6 mm							
5	Please see Item Breakup for details.				90905.43	AT Par	90905.43	
	Description:- MS angle 50x50x6 mm							
6	Please see Item Breakup for details.				37321.20	AT Par	37321.20	
	Description:- MS Flat 75x10 mm							
7	Please see Item Breakup for details.				57296.46	AT Par	57296.46	
	Description:- G.I.Nut Bolts							
8	Please see Item Breakup for details.				318957.42	AT Par	318957.42	
	Description:- Disc Insulator 11 KV 70 KN							
9	Please see Item Breakup for details.				54617.16	AT Par	54617.16	
	Description:- SSN Hardware for 0.1 Dog or AAAC 100 Sq.mm							
10	Please see Item Breakup for details.				42677.65	AT Par	42677.65	
	Description:- Strain Hardware for Dog 0.1 or Equ.AAAC.							
11	Please see Item Breakup for details.				1410601.50	AT Par	1410601.50	
	Description:- AAAC 100 mm ²							
12	Please see Item Breakup for details.				30674.00	AT Par	30674.00	
	Description:- H.T.Stay Set							
13	Please see Item Breakup for details.				27650.23	AT Par	27650.23	
	Description:- G.I.Stay Wire 7/4mm(8 SWG)							
14	Please see Item Breakup for details.				59892.55	AT Par	59892.55	
	Description:- G.I.Wire 8 SWG/ 6 SWG							
15	Please see Item Breakup for details.				2982.70	AT Par	2982.70	
	Description:- Sleeve Joints							
16	Please see Item Breakup for details.				7791.96	AT Par	7791.96	
	Description:- Danger Board in yard.							
17	Please see Item Breakup for details.				41377.38	AT Par	41377.38	
	Description:- Earthing Sets H.T							
18	Please see Item Breakup for details.				693025.80	AT Par	693025.80	
	Description:- Concreting ration 1:3:6							
19	Please see Item Breakup for details.				30852.66	AT Par	30852.66	
	Description:- G.I.Barbed Wire 'A' type.							
20	Please see Item Breakup for details.				5699.40	AT Par	5699.40	
	Description:- Black bituminous paint							
21	Please see Item Breakup for details.				15817.38	AT Par	15817.38	
	Description:- Red Oxide Paint for 2 coats							
22	Please see Item Breakup for details.				14818.44	AT Par	14818.44	
	Description:- Aluminium Paint for 1 coat							
23	Please see Item Breakup for details.				16832.20	AT Par	16832.20	
	Description:- Sundries							
24	Please see Item Breakup for details.				74095.35	AT Par	74095.35	
	Description:- Wedge connectors : DOG TO DOG or equivalent AAAC							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Schedule () III-D-II : DOUPLE POLE STRUCTURE(cut point) OF- 33 KV LINE USING13 M LONG RSJ POLE with 33 KV Isolators with EB (800 A)				4496327.12	
1	Please see Item Breakup for details.	1896043.68	AT Par	1896043.68	
	Description:- RSJ 152x152, 13 m long				
2	Please see Item Breakup for details.	663084.48	AT Par	663084.48	
	Description:- RSJ 116x100, 11 m long (For Stud)				
3	Please see Item Breakup for details.	21326.40	AT Par	21326.40	
	Description:- M.S. Flats(50 X 10mm)				
4	Please see Item Breakup for details.	104868.96	AT Par	104868.96	
	Description:- MS Channel 100x50x6 mm				
5	Please see Item Breakup for details.	113988.00	AT Par	113988.00	
	Description:- MS angle 50x50x6 mm				
6	Please see Item Breakup for details.	182380.80	AT Par	182380.80	
	Description:- 33 kv guarding channel MS100x50				
7	Please see Item Breakup for details.	45187.92	AT Par	45187.92	
	Description:- 33 kV Pin Insulators with G.I. Pins				
8	Please see Item Breakup for details.	72300.96	AT Par	72300.96	
	Description:- Strain Hardware for Dog0.1 or Equ.AAAC.				
9	Please see Item Breakup for details.	191108.16	AT Par	191108.16	
	Description:- Disc Insulator 11 KV 70 KN				
10	Please see Item Breakup for details.	70112.00	AT Par	70112.00	
	Description:- H.T.Stay Set				
11	Please see Item Breakup for details.	62530.56	AT Par	62530.56	
	Description:- G.I.Stay Wire 7/4mm(8 SWG)				
12	Please see Item Breakup for details.	30092.64	AT Par	30092.64	
	Description:- Earthing Sets H.T				
13	Please see Item Breakup for details.	14069.38	AT Par	14069.38	
	Description:- G.I.Wire 8 SWG/ 6 SWG				
14	Please see Item Breakup for details.	18315.36	AT Par	18315.36	
	Description:- G.I.Barbed Wire 'A' type.				
15	Please see Item Breakup for details.	5666.88	AT Par	5666.88	
	Description:- Danger Board in yard.				
16	Please see Item Breakup for details.	4885.20	AT Par	4885.20	
	Description:- Black Bituminous Paint				
17	Please see Item Breakup for details.	12115.44	AT Par	12115.44	
	Description:- Red Oxide Paint for 2 coats				
18	Please see Item Breakup for details.	16935.36	AT Par	16935.36	
	Description:- Aluminium Paint for 1 coat				
19	Please see Item Breakup for details.	281908.80	AT Par	281908.80	
	Description:- Concreting ration 1:3:6				
20	Please see Item Breakup for details.	660550.94	AT Par	660550.94	
	Description:- 33 KV Isolators with EB (800 A)				
21	Please see Item Breakup for details.	28855.20	AT Par	28855.20	
	Description:- Sundries				

3. ITEM BREAKUP

Schedule	Schedule I-(B) : Electrical Portion					
Item- 1	Wiring of the concealed Light / fan Point with all accessories and running earthing copper conductor as per standard practise. The switches shall be of modular type.(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site.)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	50.00	499.00	24950.00
2	2	Erection	Numbers	50.00	136.00	6800.00
					Total	31750.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 2	Supply of material and fixing and concealed wiring for (3 Plug & 3 switch on separate board) 6 A 3 pin universal socket outlet complete with 6 Sqmm PVC insulated copper conductor wires along with 14 SWG tinned copper earth wire in 25mm / 32mm dia PVC conduit pipe flush type 5A socket outlet and 5A piano type switch in GI box with PVC topsheet 5mm thick..(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	590.00	5900.00
2	2	Erection	Numbers	10.00	136.00	1360.00
					Total	7260.00
Item- 3	Supply, erection, testing & commissioning of 6A & 3 Pin Universal Modular Type Plug Socket with switch & concealed type point wiring with 2x2.5 sq mm FRLS Multistranded PVC Copper wire with all accessories and running earth on seprate board..(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	499.00	4990.00
2	2	Erection	Numbers	10.00	136.00	1360.00
					Total	6350.00
Item- 4	Wiring of Concealed 15 A 6 Pin Wall Socket Point complete with 4 Sqmm Wiring all accessories and running earthing copper conductor as per standard practice. The switches shall be of modular type for Gyser, Kettle & Fridge.(along with the all accessories and including cutting the wall / ceiling / chipping and re plastering, distempered / painted as the case may be, the same as good condition as directed by Engineer in charge at site)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	1001.00	10010.00
2	2	Erection	Numbers	10.00	130.00	1300.00
					Total	11310.00
Item- 5	Supplying & erecting CRCA sheet metal enclosures of 1.2mm thickness with 20A, 2 pin plug & earth socket and 20A, 3 pin plug top with 20A/32A single pole MCB having rated short - circuit breaking capacity (Icn) 10kA complete erected on provided angle iron/GI frame.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	4.00	1109.00	4436.00
					Total	4436.00
Item- 6	Supply, erection, testing & commissioning of Submain from switch board to single phase DP switch / DP one circuit meter comprising of 2x4 sq.mm. PVC insulated FRLS 1.1KV multistranded wire & one running earth of 2.5 sq.mm. copper conducting PVC insulation green colour of 1.1 KV grade on rigid PVC casing capping with all accessories.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply (1 ckt mtr= 1 set)	Set	50.00	156.00	7800.00
2	2	Erection (1 ckt mtr= 1 set)	Set	50.00	24.00	1200.00
					Total	9000.00
Item- 7	Supply, erection, testing & commissioning of Submain with 2x6 sqmm FRLS copper wire inside PVC Casing capping with running earth etc complete. (1 m length of submain consists one cktmtr including all accessories & 2 wire of 6 sqmm with one wire of 2.5 sqmm for earth conn).					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply (1 ckt mtr= 1 set)	Set	50.00	200.00	10000.00
2	2	Erection (1 ckt mtr= 1 set)	Set	50.00	26.00	1300.00
					Total	11300.00
Item- 8	Supply, erection, testing & commissioning of energy efficient 1x18 W indoor fitting LED batten with extruded aluminium housing with integrated LED Driver/Tube complete and associated accessories complete.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	18.00	415.00	7470.00
2	2	Erection	Numbers	18.00	105.00	1890.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	9360.00
Item- 9	SETC of LED street Light Roadway fittings in aluminium PDC housing, toughened glass cover with IP66 protection, Wattage-72 watts, input voltage-240 volts ac, 50Hz. Complete with PIR sensor based with Auto dimming facility.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	7906.00	79060.00
2	2	Erection	Numbers	10.00	70.00	700.00
					Total	79760.00
Item- 10	LED Flood light fittings of 250watt with IP 66 protection and 5 years warranty as per attached GEM specification.Required make- Halonix or similar. 250W LED Luminaire for flood light Brand:OREVA Category Name & Quadrant: Led Luminaire (for flood Light) IS 10322 IS:16107 (Q3) & 250 WATT IP 66 Flood Light with 5 Year warranty					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	9426.00	94260.00
2	2	Erection	Numbers	10.00	212.00	2120.00
					Total	96380.00
Item- 11	Supply, erection, testing & commissioning of Lighting Circuit Board, Double Door Powder coated with locking arrangement consisting 32 A DP ELCB/RCBO as I/C and 6 Nos x 6 A SPMCB and 2 Nos x 20A O/G SPMCB Complete.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	5609.00	11218.00
2	2	Erection	Numbers	2.00	636.00	1272.00
					Total	12490.00
Item- 12	Supply, erection, testing & commissioning of 7 Mtr high (clear height) galvanised octagonal pole with foundation bolts having bottom of 130 mm A/F, top 70 mm A/F on provided foundation.(Along with 2 pole RCBO 6A, with 30 mA sensitivity).					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	14228.00	142280.00
2	2	Erection	Numbers	10.00	1046.00	10460.00
					Total	152740.00
Item- 13	Providing & erecting epoxy outdoor / indoor end termination kit for LT XLPE armoured cable 2.5 to 16 sq mm., with necessary material as per specification					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	3.00	2102.00	6306.00
					Total	6306.00
Item- 14	Providing & erecting epoxy outdoor / indoor end termination kit for LT XLPE armoured cable 25 to 50 sq mm., with necessary material as per specification					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	2.00	2545.00	5090.00
					Total	5090.00
Item- 15	Supply, erection, testing & commissioning of Astronomical Timer 3Ph with multitiming setting including suitable contactor of 100 Amp.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	15453.00	30906.00
2	2	Erection	Numbers	2.00	1074.00	2148.00
					Total	33054.00
Item- 16	Supply, fixing, testing & commissioning of energy efficient BLDC motor industrial exhaust fan of size 300 mm (12") sweep and standard accessories, as per specifications in Annexure II. (Minimum Warrantee - 2 years)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	2.00	6591.00	13182.00
					Total	13182.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 17	Supply & fixing of 1200 mm sweep energy saving BLDC ceiling fan with Remote, 300mm length of down rod (without shackle), input power not more than 28W, minimum 1.1mm aluminum blade material, double ball bearing, 2 canopy, to be operated in AC single phase supply. as per specification.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	10.00	2743.00	27430.00
					Total	27430.00
Item- 18	Supply, erection, testing & commissioning of maintenance free earth as per RDSO specification no. RDSO/PE/SPEC/ PS/0109-008(REV '0') with improved earthing enhancing compound and exothermic welding					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	12965.00	25930.00
2	2	Erection	Numbers	2.00	2048.00	4096.00
					Total	30026.00
Item- 19	Supply, laying,connecting &commissioning of 50x6 mm / 40x5 mm /25x6 mm thick GI Strip for earth pit as per the directions of engineer at site					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Kg	50.00	75.00	3750.00
					Total	3750.00
Item- 20	SETC of 2 core 10 sqmm Armoured Aluminium Cable with continuous GI earth wire complete erected with glands and lugs on wall/truss etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	200.00	163.00	32600.00
2	2	Erection	Metre	200.00	25.00	5000.00
					Total	37600.00
Item- 21	Supply of 4 core 25 sqmm armoured XLPE Cable.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	200.00	232.00	46400.00
					Total	46400.00
Item- 22	Supply of LT XLPE Armoured 4 Core 50 Sqmm Aluminium cable as per relevant IS.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	200.00	398.00	79600.00
					Total	79600.00
Item- 23	Trenching & refilling of LT/HT/ Various sizes of PVC / XLPE cables- Along the Road (Size - 900mm x 300mm)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	200.00	207.00	41400.00
					Total	41400.00
Item- 24	Digging of cable trench 300/450 mm x 1000 mm in RCC/PCC/hard soil & refilling as per specification and requirement at the site.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	100.00	368.00	36800.00
					Total	36800.00
Item- 25	Transportation, Laying, Installation, terminating, testing and commissioning of LT/HT cable of sizes 10 sqmm to 400 sqmm in existing trench, pipe or on structure.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	300.00	30.00	9000.00
					Total	9000.00
Item- 26	Erection,testing and commissioning of cables other than trench i.e.Wall/Truss including clamp, GI wire and hardware					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	100.00	68.00	6800.00
					Total	6800.00
Item- 27	Supply & laying of GI pipe Class B, ISI marked under road /Clamping with erecting pole or wall as per technical specification & drawing for passing cable.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Metre	10.00	202.00	2020.00
					Total	2020.00
Item- 28	Supply and laying of RCC half round pipe 150 mm ID & 1 mtr length.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	81.00	8100.00
2	2	Erection	Metre	100.00	12.00	1200.00
					Total	9300.00
Item- 29	Supply and laying of RCC Hume Pipe of size 6"(150mm) dia 2 mtr. Length.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	615.00	1230.00
2	2	Erection	Numbers	2.00	92.00	184.00
					Total	1414.00
Item- 30	Supply, erection of RCC Type cable route marker with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	10.00	499.00	4990.00
					Total	4990.00
Item- 31	Supply & Erection of RCC Warning Cover and refilling the cable trench in an approved manner.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	292.00	2920.00
2	2	Erection	Numbers	10.00	131.00	1310.00
					Total	4230.00
Item- 32	"Supply, installation and commissioning of RO water purifier with pre filter. Capacity: 50 LPH. Specification as described.Also Fully automatic with auto cut off RO+UV+UF Potable Water Purification System "					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	24500.00	24500.00
					Total	24500.00
Item- 33	Supply of Steel Almirah, Size - 6 ft x 3 ft					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	9291.00	9291.00
					Total	9291.00
Item- 34	Table for operator similar to Godrej Model					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	10895.00	32685.00
					Total	32685.00
Item- 35	Chair for operator similar to Godrej Model					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	6537.00	65370.00
					Total	65370.00
Item- 36	Supply of tool storage box Dimensions WxHxD(cm) 91.6x198x48 for kept sub station tools. GodrejProduct ID:30161803SD00206					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	28307.00	28307.00
					Total	28307.00
Item- 37	Supply of L Shape test bench Wooden and Metal Godrej Maestro Desk for for sub station instrumenttest bench with 4 nos modular type 6/16A socket wiring arrangemnts.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Each	1.00	40234.00	40234.00
					Total	40234.00
Item- 38	Supply and installation of Chairs revolving type for work station as per specification					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	9239.00	9239.00
					Total	9239.00
Schedule	Schedule I-(A) : 2 X 5 MVA 33/11 KV Substation					
Item- 1	Supply of 33 KV HT panel [2 (IC)+3 (OG)+ (1 BC)] AS per technical specification. 33 KV, 1250 A, 26.3 KA/ 3 SEC HORIZONTAL withdraw able VACUUM CIRCUIT BREAKER , WITH SPRING CHARGING MOTOR 230 VAC , CLOSING COIL & TRIPPING COILS RATED 110 V DC 4 NO + 4 NC, Handles for VCB, Current Transformer RATIO : /5 A CORE 1 : 10 VA, CL : 1.0 CORE 2 : 10 VA, CL : 5P20 (Fixed type) (16 Nos.), Potential Transformer 33000V/3/110V/3/110V/3 CORE 1 : 50 VA, CL : 1.0 (Fixed type) (06 Nos.), Numerical relay having 3 O/ C+1 E/F PROTECTION RELAY, (50/51/50N/51N/95) (04 Nos), Numerical relay having 3 O/ C+1 E/F PROTECTION RELAY,(50/51/50N/51N/95/27/59) (02 Nos.), Arc Flash relay with 3 Sensor Arrangement (05 Nos.), Master Trip relay - Hand Reset (86) (06 Nos.), Auxilary relay for transformer 3 Element (02 Nos.), Auxilary relay Plug In type for Contact Multiplier 52X OTI/WTI/MOG & Transformer auxilary relay operation (20 Nos.), Indication - {BREAKER ON - Red (06 Nos.), BREAKER OFF - Green (06 Nos.), AUTO TRIP INDICATION - Amber (06 Nos.), SPRING CHARGE HEALTHY - Blue (06 Nos), TRIP CIRUIT HEALTHY - White (06 Nos.), BREAKER TEST POSITION - Green (06 Nos.), BREAKER SERVICE POSITION - Red (06 Nos.), RYB INDICATION (Red / Yellow / Blue) (02 Nos.),} Metering - {Digital Multifunction meter Class 0.5 with RS485 Communication (05 Nos.), Digital ammeter (05 Nos.), Digital voltmeter (02 Nos.), Temp Sensor for Heat Riseing (12 Nos.)}, Standard Electrical Accessories - {DC ON/OFF SWITCH (06 Nos.), AC ON/OFF SWITCH (06 Nos.), 80W STRIP HEATER (06 Nos.), THERMOSTAT (06 Nos.), Door Limit Switch (06 Nos.), Toggle Switch (06 Nos.), CUBICLE ILLUMINATING LAMP (06 Nos.), 6A, 230V, 3 PIN PLUG & SOCKET (06 Nos.), 25 Amp trip - Neutral Close Type Breaker Control switch (06 Nos.), LOCAL/REMOTE SELECTOR SWITCH (05 Nos.), Annunciator with Accept/Reset/Test push button 16 W (05 Nos.), Hooter 96 X 96 (05 Nos.), MCB 10A, 2P, 110VDC, for DC circuit (06 Nos.), MCB, 10A, 240VAC, 2P for AC circuit (06 Nos.), MCB, 6A, 240VAC, 2P (06 Nos.), MCB 25 A, 4P MCB (06 Nos.), Fuse Link 2A/4A for CB control/Indication & PT secondary ckt. (02 Nos.), Spout & Shutter Assembly (06 Nos.), Power Pack 230 VAC - 110 VDC with 30 Min back up (06 Nos.), Surge Arrester Set of 3 for Incomer (02 Nos.)}, Inhouse Component - {Enclosure OUTDOOR Type (2 IC + 1 BC + 1BR + 3 OG) (07 Nos.), Suitable Busbar -Aluminium 80x10 x2 (07 Nos.), Earthing Busbar - Copper (07 Nos.), Wires other accessories (07 Nos.)}.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	8791000.00	8791000.00
2	2	Erection	Set	1.00	20197.00	20197.00
					Total	8811197.00
Item- 2	Design, fabrication,erection, testing and commissioning of 33KV out door type, 1250 A triple pole, rotating type Air Break Isolator with earthing switch (Conforming to IS 1818/72 or latest complete in all respect) on isolators structure with suitable arrangement as required and as per direction of site-in-Charge.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Set	2.00	45382.00	90764.00
					Total	90764.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 3	Supply, fitting, fixing of 33 KV, 400 Amps, 25 KA Air Break vertical mounting Gang operating switch. The Gang Operating Switch shall conform to the following standards: (i) IS-9920 (Part I to V) (ii) IS 2544/1973 (iii) IS2633. The Insulators should be 22 KV /24 KV class (for 33KV AB Switches) Post Insulators complete with pedestal cap duly cemented to be used in the AB Switch Set conforming to IS-2544/1973. The operating mechanism shall be suitable for manual operation from the ground level and shall be so designed that all the three phases shall open or close simultaneously. The Switches shall be robust in construction, easy in operation and shall be protected against over travel or straining that might adversely affect any of its parts. The required base M.S. Channel, phase coupling rod, operating rod with intermediate guide braided with flexible electrolytic copper, tail piece of required current carrying capacity and operating mechanism with ON' & OFF' positions shall be provided. The operating rod shall be medium gauge of 32mm diameter nominal bore G.I. pipe single piece 6 meters. The phase coupling rod for gang operation shall medium gauge 25mm dia nominal bore G.I. Pipe. Rotating post insulators shall be provided with suitable bearing mounted on a base channel with 6 mm thick thrust collar and 6mm split pin made out of stainless steel. The operating down rod shall be coupled to the spindle (minimum dia - 32mm) for gang operation through another suitable bearing by two numbers 10mm dia through stainless steel bolts with double nuts. The post insulators should be fixed with the base channel using Galvanized Nuts and Bolts. Suitable arcing horns shall be provided for breaking the charging current horn shall be made of 10 mm dia G.I. Rod with spring assisted operation. The required Test certificates of the Gang operated switch should be provided					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Set	2.00	31670.00	63340.00
Total						63340.00
Item- 4	Supply, fitting, fixing of 33 KV Dropout fuse, 400Amps, 3 pole with 4Nos 22/24KV post insulator per phase. The Drop Out fuse unit shall conform to the following standards: (i) IS-5792- 1973 (For high voltage expulsion fuses & similar fuses) (ii) IS-2544-1973 (for porcelain post insulators) (iii) IS-9385-1979 or its latest amendments if any. (iv) IS-2633-1979 (For Galvanization of ferrous parts). The Drop out Fuses shall have adjustable arcing horns made of solid copper rod having 8.23 mm dia. The horns shall be fitted with screwing devices with fly nuts for fixing and tightening the fuse wire. It shall have robust terminal connector 5s of size 80mm x50 mm x 8mm made of copper casting (95% minimum copper composition) duly silver plated with two numbers of 12 mm dia brass bolts and double nuts with flat brass washers. The connector should be capable of connecting crimpable conductor upto 232 Sq.mm. size (ACSR/ AAAC) with bimetallic solderless sockets .The Drop Out Fuse Set shall suitable for horizontal mounting on sub-station structures. . All metal (ferrous) parts shall be galvanized and polished. Only post insulator (original cemented and not pin insulators shall be used for the Drop Out Fuse Set.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Set	2.00	16411.00	32822.00
Total						32822.00
Item- 5	Supply, installation, commissioning and testing of set of HT VCB panel board 250 MVA, 400/630 Amps capacity, degree of protection -P4x, consisting of : Incoming -02 nos, outgoing - 04nos, Buscoupler - 01Nos - 11 KV, 13.1 Ka, 3 pole Vacuum circuit breaker conforming to IS : 13118 (latest version) with PT having ratio of 11KV/110V AC, Electronic protection relay with 02 over current & 01 earth fault protections, electronic tri-vector meter and ammeter with selector switches, LED type indication lamps on 3 phases, busbar chamber with 3 phase copper busbars, strip type heater, double copper wound CTs and suitable cable end box, 24VDC, 135 AH battery set & single phase battery charger, VCB panels to be supplied as per technical specifications attached.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	3275301.00	3275301.00
Total						3275301.00
Item- 6	Supply, fabrication, fixing of MS channels and angles of sizes ISMC 150 x 75 mm x 6 mm and ISA 75 x 75 mm x 6 mm (or) any other dimension as per site condition, including necessary clamps, bolts, nuts, washers including painting with two coat of red oxide, one coat of aluminum etc. for Double pole structure with RSJ/PSCC pole mentioned above item.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	MT	0.50	68653.00	34326.50
2	2	Erection	MT	0.50	4369.00	2184.50
Total						36511.00
Item- 7	Supply, fabrication, galvanization and erection of steel gantries, portals, supporting structures, earth screen post structure and small parts steel work as per direction of site engineer.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply & Erection	MT	0.50	80615.00	40307.50
					Total	40307.50
Item- 8	Supply and stringing of 33 KV HT OH mains with ACSR 'Panther' conductor including binding and jumper connections etc.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	50.00	167.00	8350.00
2	2	Erection	Metre	50.00	16.00	800.00
					Total	9150.00
Item- 9	Supply, erection, testing and commissioning of Aluminium tubular bus bar (Al-Alloy 63401 grade) nominal size 1-1/2" (outer dia- 48.26 mm, inside dia-40.89 mm, thickness 3.69 mm), medium gauge,length - 20 mtr, confirming to IS:5082 & IS:2673 with various bus bar connector complete with stainless steel nut, bolts, plan & spring washer and other requisite accessories					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Metre	20.00	794.00	15880.00
					Total	15880.00
Item- 10	Supply and installation of 33KV Post type Insulators with all connected accessories.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Each	6.00	982.00	5892.00
2	2	Erection	Each	6.00	55.00	330.00
					Total	6222.00
Item- 11	Supplying and erection of single piece nonlinear resistor type lightning arrester suitable for 3 wire, 33 KV overhead lines with rated voltage 30 KV (rms) with a nominal discharge current rating of 10 KA (station class) and complete with galvanised clamping arrangement, G.I.bolts, nuts, washers etc. as required.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	12.00	11365.00	136380.00
					Total	136380.00
Item- 12	Supply, fitting, fixing of 33 KV 10 KN Pin Insulator (polymeric type) with 900 mm crepage distance including all hardware materials					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	6.00	472.00	2832.00
					Total	2832.00
Item- 13	Supply, fitting, fixing of 33 KV 70 KN Disc Insulator (polymeric type) including all hardware materials.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	6.00	768.00	4608.00
					Total	4608.00
Item- 14	Supply, Installation, testing, commissioning of Current Transformer, 1-ph, 33 KV, 100 A, 25 KAwith 120% extendedcurrent rating, systemvoltage 36 KV.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	6.00	77580.00	465480.00
					Total	465480.00
Item- 15	Supply, Installation, testing,commissioning of 33 KV/110V, Potential transformer (1-ph.),system voltage 36 KV.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	6.00	56952.00	341712.00
					Total	341712.00
Item- 16	Supply & fabrication of steel structures for installation of CT, PT & VCBs as per details					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	MT	1.00	66480.00	66480.00
					Total	66480.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 17	Supply,installation,testing andcommissioning ofoutdoor 33/11 KV, 5 MVA (5000KVA), 50C/S, 3 phase, Oilimmersed, ONAN,Copper wounded, automatic on loadtap Changermotor operated 415 V, 50 Hz AC,17 tapings of 5% voltage on Higherside and variation+5% to -15% instep of 1.25%,outdoor type as per IS:2026 or latest with OLTC &RTCC, and with all connected accessories as per directions of Engineer at site.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Set	2.00	7748647.00	15497294.00
					Total	15497294.00
Item- 18	Supply and installation of 3-PH 63 kVA 33 kV/433 V Distribution Transformer with BIS EE Level-3 as per uploaded specification. Makes:Mahindra/Servokon/Kirloskeronly					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	103046.00	103046.00
2	2	Erection	Numbers	1.00	1965.00	1965.00
					Total	105011.00
Item- 19	1) SETC of 20 KVA Online UPS with isolation transformer for lighting load. Phase: 3PH-1PH Warranty: 2 Years from Supply - 01 Nos, 2) SETC of 100AH/12V Batteries for your 2 Hrs. battery backup proposed load. Make: Exide Warranty: 2 years from supply - 32 Nos, 3) SETC of Battery Rack & Link - 01 Nos, 4) transportation & Installation charges - 01 Nos.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	477074.00	477074.00
					Total	477074.00
Item- 20	Earth work in excavation as per the instructions of site engineer and dumping at embankment site or spoil heap,within railway land, including 50m lead and 1.5m lift, etc., -All kinds of soils					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	cum	500.00	108.00	54000.00
					Total	54000.00
Item- 21	Supply, fabrication, fixing and erection of MS Work of miscellaneous size and for cable tray etc. including painting complete.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	500.00	83.00	41500.00
2	2	Erection	Kg	500.00	14.00	7000.00
					Total	48500.00
Item- 22	Supply of 3 core 120 mm ² 33 KV XLPE UG armored Aluminum Cable, confirming of IS7098 Pt.II /1985 or latest.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	300.00	1748.00	524400.00
					Total	524400.00
Item- 23	Supply and erection of 33 KV heat shrink cable straight through jointing kit upto 3 core 300Sq.mm.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	4.00	51315.00	205260.00
					Total	205260.00
Item- 24	Supply , installation,testing & commissioning of 33 KV Outdoor type heat shrinkable cable termination kit upto 3 core 300 Sq.mm.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	20810.00	208100.00
2	2	Erection	Numbers	10.00	2081.00	20810.00
					Total	228910.00
Item- 25	Supply and making indoor cable end termination shrinkable jointing kit complete with all accessories including lugs with heat suitable for 120 sq.mm of 3 core, XLPE aluminium conductor cable for 33 KV grade as required.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Set	20.00	28549.00	570980.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	570980.00
Item- 26	Supply of cable 3 core 300Sq.mm XLPE insulated Al armored cable 11 KV grade.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	300.00	2412.00	723600.00
					Total	723600.00
Item- 27	Supply of 3 core 240 mm ² 11KV HT XLPE UG armored Aluminum Cable, confirming of IS 7098 Pt.II /1985 or latest.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	1776.00	177600.00
					Total	177600.00
Item- 28	Supply of 3 core 185 mm ² 11KV HT XLPE UG armored Aluminum Cable, confirming of IS 7098 Pt.II/1985 or latest.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	1424.00	142400.00
					Total	142400.00
Item- 29	Supply, fixing, connecting, testing & commissioning of outdoor type Heat shrinkable cable termination kit for outdoor type 11 KV 3 core 240-300 sq mm HT XLPE cable with all connected accessoriesconfirming to IS 13573/1992 or latest as per the directions of Engineer at site.Make:Raychem/RPG/Denson only					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	10.00	7428.00	74280.00
2	2	Erection	Set	10.00	1027.00	10270.00
					Total	84550.00
Item- 30	Construction of Reinforced concrete (Cable duct with 1:2:4 RCC concrete) providing with angular frames and covers as per the directions of engineer at site.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	cum	200.00	5179.00	1035800.00
					Total	1035800.00
Item- 31	Construction providing of Cable trench & covers with1:2:4 RCC concrete as per the directions of engineer at site					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Sqm	100.00	1486.00	148600.00
					Total	148600.00
Item- 32	Supply of 11kV 3 core 95 sqmm HT Aluminium armoured cable conforming to IS: 7098-Part 2 :2011					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	816.00	81600.00
					Total	81600.00
Item- 33	Supply of 11 kV 3 core 120 sqmm HT Aluminium armoured cable conforming to IS: 7098-Part 2 :2011					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	1545.00	154500.00
					Total	154500.00
Item- 34	Supply, erection, testing and commissioning of 11 kV HT outdoor heat shrinkable cable jointing/ terminating Kit suitable for 3 core 70/95/120/185 Sq.mm Aluminium armoured XLPE cable.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	20.00	12313.00	246260.00
2	2	Erection	Numbers	20.00	1516.00	30320.00
					Total	276580.00
Item- 35	Supply, erection, testing & commissioning of 11 KV HT Indoor type end termination kit suitable for HT XLPE Cable.					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	20.00	9813.00	196260.00
2	2	Erection	Numbers	20.00	568.00	11360.00
					Total	207620.00
Item- 36	Excavation of cable trench 30 cm wide x 120 cm deep in all types of soils for laying of HT UG/XLPE cable as per Railway specification or as per the directions of the engineer at site.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Metre	300.00	168.00	50400.00
					Total	50400.00
Item- 37	Cutting of esphalted road/ concrete/ cement/under the track etc., and excavation of cable trench of wide 40cm x 120cm for laying of HT cable. After laying of cable the trench should be brought to its original position by providing tar/ concrete/ cement as per the site conditions and as per directions of Rly Engineer.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Metre	50.00	289.00	14450.00
					Total	14450.00
Item- 38	Transportation, Laying, Installation, terminating, testing and commissioning of LT/HT cable of sizes 10 sqmm to 400 sqmm in existing trench, pipe or on structure.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	950.00	30.00	28500.00
					Total	28500.00
Item- 39	Erection,testing and commissioning of cables other than trench i.e.Wall/Truss including clamp, GI wire and hardware					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Erection	Metre	50.00	68.00	3400.00
					Total	3400.00
Item- 40	Supply & laying of GI pipe Class B, ISI marked under road /Clamping with erecting pole or wall as per techincal specification & drawing for passing cable.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Metre	46.00	202.00	9292.00
					Total	9292.00
Item- 41	Supply and laying of HDPE (High Density Polyethylene pipe) pipe of PE-80 Grade in PN- 4 outer dia of HDPE pipe 160mm (nearest 6" dia) and wall thickness minimum 6.2mm maximum 7.1mm with joints,bens, elbows etc. including all other connected accessories.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	619.00	61900.00
2	2	Erection	Metre	100.00	43.00	4300.00
					Total	66200.00
Item- 42	Supply and laying of HDPE pipe of PE-80 grade in PN-4 outer dia of HDPE pipe 110mm (nearest 4"dia) and wall thickness minimum 4.1 mm maximum 4.3 mm with 'T' joints, bends, elbows etc.including all other connected accessories.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	150.00	282.00	42300.00
2	2	Erection	Metre	150.00	21.00	3150.00
					Total	45450.00
Item- 43	Supply and laying of RCC half round pipe 150 mm ID & 1 mtr length.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	81.00	8100.00
2	2	Erection	Metre	100.00	12.00	1200.00
					Total	9300.00
Item- 44	Supply and laying of RCC Hume Pipe of size 6"(150mm) dia 2 mtr. Length.					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	20.00	615.00	12300.00
2	2	Erection	Numbers	20.00	92.00	1840.00
					Total	14140.00
Item- 45	Supply, erection of RCC Type cable route marker with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	20.00	499.00	9980.00
					Total	9980.00
Item- 46	Supply, erection, testing & commissioning of RCC warning cover of size 18" X 7"X1.5" in an approve manner					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	100.00	74.00	7400.00
2	2	Erection	Metre	100.00	8.00	800.00
					Total	8200.00
Item- 47	Construction of plinth for erecting the panel/DG set/VCB with stone / brick masonry with all connected accessories.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cum	100.00	1636.00	163600.00
2	2	Erection	cum	100.00	655.00	65500.00
					Total	229100.00
Item- 48	Mass concreting of erected poles/ strut poles/ stays poles and stay sets with CC (1:3:6) using 40 mm size metal including the cost of metal, sand, cement and curring etc as per directions of site engineerand site condition.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cum	50.00	2487.00	124350.00
2	2	Erection	cum	50.00	655.00	32750.00
					Total	157100.00
Item- 49	Supply and Spreading of 20 mm ballast in switch yard of different Sub-Station.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cum	200.00	1090.00	218000.00
2	2	Erection	cum	200.00	152.00	30400.00
					Total	248400.00
Item- 50	Supply, erection, testing & commissioning of maintenance free earth as per RDSO specification no. RDSO/PE/SPEC/ PS/0109-008(REV '0') with improved earthing enhancing compound and exothermic welding					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	24.00	12965.00	311160.00
2	2	Erection	Numbers	24.00	2048.00	49152.00
					Total	360312.00
Item- 51	Supply, laying,connecting &commissioning of 50x6 mm / 40x5 mm /25x6 mm thick GI Strip for earth pit as per the directions of engineer at site					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Kg	250.00	75.00	18750.00
					Total	18750.00
Item- 52	Supply and provision of earthing with copper earth plate 600mm x 600mm x3mm thickincluding accessories, and providing masonry enclosure with cover plate having lockingarrangement and water pipe of 2.7 meter long etc. with charcoal/coke and salt as required					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	20.00	13031.00	260620.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

						Total	260620.00
Item- 53	Supply and provision of 25mmx 5mm copper strip in 40mm dia G.I pipe from earthelectrode including connection with brass nut, bolt, spring, washer excavation and re-fillingetc. as required						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply & Erection	Metre	50.00	1288.00	64400.00	
						Total	64400.00
Item- 54	Provision and making of earth mesh 500 mm deep under the earth in 32x34 Sq.M area of switching yard as per RDSO drawing no. SKE 3975 attached including supplying and providing 35x6 mm copper strip at 3 mtr interval. Earthing the mat with copper plate size: 600 x600 x 6 mm (total 16 Nos.) 15' deep at each corner for connecting the equipment sand fencing including earth work, supply of copper plates, nuts, bolts and brazing of copper strip as required.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply & Erection	Numbers	1.00	492758.00	492758.00	
						Total	492758.00
Item- 55	Supply of earth pit materials and construction of earth pit as per IS 3043:1987 specification. This item also includes of supply and erection of CI pipe of size of 100mm inner diameter, 13mm thickness and 3000mm length. This work also includes of fabrication and fixing of GI strips for earthing connection. Excavated earth pit should be filled by mixture of coke/charcoal, salt and sand up to top. Provision of brick masonry chamber of size 650mmx650mm and depth up to 1000mm including light type CI cover frame and applying 12mm thick cement plaster in 1:3 inside and to all the exposed faces up to 300mm below. Foundation level, curing etc., All required materials for this job such as CI pipe cover with frame, salt, cement sand, charcoal gravel, bricks etc required bolts, nuts and double washers, number plates or painted plates. Tentative quantity of salt and charcoal shall be of 2.5CMt. The CI pipe should be painted with 2 coats of bitumen paint as per the directions of Rly engineer at site. Note: The work (Earthing arrangement with all accessories) should be strictly done as per IS 3043:1987 specification or latest.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply & Erection	Each	20.00	9366.00	187320.00	
						Total	187320.00
Item- 56	Fencing arrangements to the 33kV HT New sub station yard NOTE:- For the details under tender document and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(a) Supply and erection of Fencing Panels						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Metre	177.00	1647.00	291519.00	
2	2	Erection	Metre	177.00	218.00	38586.00	
						Total	330105.00
Item- 57	Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(b) Supply and erection of Fencing Uprights						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	MT	1.80	55459.00	99826.20	
2	2	Erection	MT	1.80	2326.00	4186.80	
						Total	104013.00
Item- 58	Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(c) Supply and erection of Anti climbing device						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Metre	179.00	113.00	20227.00	
2	2	Erection	Metre	179.00	33.00	5907.00	
						Total	26134.00
Item- 59	Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C'/sheet No. 1 & 2 and ETI/PSI/104(d) Foundation of upright Type-I						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	cum	8.00	2435.00	19480.00	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	2	Erection	cum	8.00	546.00	4368.00
					Total	23848.00
Item- 60	Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C/sheet No. 1 & 2 and ETI/PSI/104(e) Foundation of upright Type-II					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cum	6.00	2435.00	14610.00
2	2	Erection	cum	6.00	546.00	3276.00
					Total	17886.00
Item- 61	Fencing arrangements to the 11KV HT New sub station yard NOTE:- For the details under tenderdocument and please refer RDSO drawing Nos. ETI/C/0186 MOD'C/sheet No. 1 & 2 and ETI/PSI/104(f) Supply and erection of Gate with lock					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	20.00	1595.00	31900.00
2	2	Erection	Metre	20.00	133.00	2660.00
					Total	34560.00
Item- 62	Coping of poles stay poles /stays with a height of 470mm x450mm x450mm or suitable size withCC(1:3:6) using 20mm size metal including the cost of metal sand, cement and curring etc as perdirections of site engineer and site condition.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	2727.00	5454.00
2	2	Erection	Numbers	2.00	655.00	1310.00
					Total	6764.00
Item- 63	Supply of portable Fire Extinguishers dry chemical type 9/10 Kgs. Capacity fitted with gun metal cap.Dry chemical powder 9/10 Kgs conform to IS:4303 and carbondioxide conform to IS 4947.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	14038.00	84228.00
					Total	84228.00
Item- 64	Supply of Fire extingisher 5 KG capacity Dry type.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	3719.00	37190.00
2	2	Erection	Numbers	10.00	44.00	440.00
					Total	37630.00
Item- 65	Supply and Erection of Fire Bucket Stand with 4 Nos Bucket Each capacity 9 Ltr including Locking Arrangement.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	6.00	2398.00	14388.00
2	2	Erection	Set	6.00	131.00	786.00
					Total	15174.00
Item- 66	Suuply and installation of Insulated Rubber Matting (33 KV & 11KV) non skid type with fluted type and plain border size 2 mtr X 1 mtr X 12 mm thick.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	5.00	1743.00	8715.00
					Total	8715.00
Item- 67	Supply of Tool Kit No. 1002 for Tube wells of size of Box 560x280x310mm with total no. of content of Tools chest 32 Nos (Bi hexagon ring spanner 21x23mm -2 No, Double open End spanner 6x7-20x22mm, 7/16x1/2ww-8No, Heavy duty pipe wrenches 350&450mm-2No, Grip lock plier 250mm-2No, Screw driver Engineer pattern 5x75 & 8x200mm-1No. Ball pein Hammer 500gms-2no,Adjustable wrench 300mm-1no, Bolt Die set 1/2"BSW-1no, Chain pipe vice 50mm-1no, Cold Chisel150mm-1no, Flat File 250mm with handle-1no, Hacksaw Frame 300mm-1no, Spirit Level 200mm-1no, Measuring Tape Steel 2Mtr-1no, Oil Can -1no, Pipe Clamp-1no, Die set 1.1/4-1.1/2 BSP-2no,Tommy Bar 460mm-1no, Wire Brush-1no, Tool Chest-1no. of M/s. Tappary/ Everest make only					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	33924.00	33924.00
					Total	33924.00
Item- 68	Supply of Air velocity and Ambient temperature and Surface temperature and Humidity VaneAnemometer.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	26215.00	26215.00
					Total	26215.00
Item- 69	Supply of 33KV discharge rod of standard make with suitable top and bottom copper clamps with connecting cables as approved by Rly. Authority					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	2581.00	7743.00
					Total	7743.00
Item- 70	Supply of Fluke 362 Clamp Meter With Light					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	10355.00	10355.00
					Total	10355.00
Item- 71	Supply of Digital Megger 500 V.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	7075.00	7075.00
					Total	7075.00
Item- 72	Supply of Digital Megger 2500 V.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	14436.00	14436.00
					Total	14436.00
Item- 73	Price for supply of hand drive metal body generator type insulation tester megger 5000 V / 20000 Mega ohms.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	15000.00	15000.00
					Total	15000.00
Item- 74	Supply of Digital Clamp on Earth Tester.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	52705.00	52705.00
					Total	52705.00
Item- 75	Supply of infrared Thermometer.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Each	1.00	8083.00	8083.00
					Total	8083.00
Item- 76	Supply and fixing of Surveillance security system with 4Pcs 5MP Full HD 8CH DVR Bullet Cameras, 2Pieces Dome Camera, 1TB Hard Disc, CCTV Wire Roll, Power Supply and All Required Connectors.Model No.Hikvision (DS-7208 HQHI-M1/S) /(DS-7B08HQHI-K1) 8CH DVR					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	24903.00	24903.00
2	2	Erection	Set	1.00	2185.00	2185.00
					Total	27088.00
Item- 77	Supply and fixing of Surveillance security system with 4Pcs 5MP Full HD 8CH DVR Bullet Cameras, 2Pieces Dome Camera, 1TB Hard Disc, CCTV Wire Roll, Power Supply and All Required Connectors.Model No.Hikvision (DS-7208 HQHI-M1/S) /(DS-7B08HQHI-K1) 8CH DVR					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Numbers	1.00	41634.00	41634.00
					Total	41634.00
Item- 78	Supply of hp inkjet Colour Computer Printers for A4 paper size Brand: HP					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	13890.00	13890.00
					Total	13890.00
Item- 79	Supply & erection of Danger Board for 33/11 KV system					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	25.00	161.00	4025.00
					Total	4025.00
Item- 80	Supply of Shock treatment boards.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	4.00	65.00	260.00
					Total	260.00
Item- 81	Supply & erection of Substation layout board made of GI sheet and rigid frame					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Each	1.00	779.00	779.00
					Total	779.00
Item- 82	Survey, design and preparation of drawings of 33/11KV sub-station including over head line					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	33423.00	33423.00
					Total	33423.00
Item- 83	Supply and Erection of Sub station Name board including required fitting.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply & Erection	Numbers	1.00	13485.00	13485.00
					Total	13485.00
Item- 84	Preparation of Substation Schematic Diagram on Auto Cad with one set of soft copy and 2 set of hard copy in hard glass frame for display in Sub-Station.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	2647.00	2647.00
					Total	2647.00
Item- 85	Supply of Aluminium extension Ladder (light weight) 20' closed height and 30' extended height					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	8856.00	17712.00
					Total	17712.00
Item- 86	Supply of Aluminium Ladder 12' long (Platform type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	2698.00	5396.00
					Total	5396.00
Item- 87	Supply of Aluminium telescopic ladder, heavy duty with holding rubber, foldable with equal steps, 12 to 13 Feet height with push button type system ladder					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	6909.00	6909.00
					Total	6909.00
Item- 88	Supply of GREEN PANEL PLYWOOD 2400X1200 mm MR Plywood					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Square Foot	500.00	13.00	6500.00
					Total	6500.00
Item- 89 Supply of Safety Belt						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	278.00	1668.00
					Total	1668.00
Item- 90 Supply of First Aid Box including medicines.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	1720.00	3440.00
					Total	3440.00
Item- 91 Supply Rubber hand globes for 33KV (for both hands) .						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	4.00	850.00	3400.00
					Total	3400.00
Item- 92 Supply of battery operated Saw cutting having Weight less than 5 Kg Complete.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	26569.00	26569.00
					Total	26569.00
Item- 93 Supply of Heavy duty Hammer Drill Machine of approved make.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	7238.00	7238.00
					Total	7238.00
Item- 94 Supply of Hydraulic crimping tools capacity 10 mm2 to 185 mm2 dies: R-1 to R13.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	16346.00	16346.00
2	2	Erection	Numbers	1.00	163.00	163.00
					Total	16509.00
Item- 95 Portable hand held electric air blower (Detail specification attached.) DEWALT Fibre Body Handheld Electric Blower, Warranty 12 months						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	4506.00	4506.00
					Total	4506.00
Item- 96 Long Range 1KM Torch Light Beam Battery Included 1500 Lumens.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	6357.00	6357.00
					Total	6357.00
Schedule Schedule II-A-I : 9-a) Structure						
Item- 1 Structure for 33 KV L.A.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	250.00	82.60	20650.00
2	2	Erection	Kg	250.00	4.13	1032.50
					Total	21682.50
Item- 2 Structure for 33 KV CT						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	315.00	82.60	26019.00
2	2	Erection	Kg	315.00	4.13	1300.95
					Total	27319.95

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 3 Structure for 33 KV PT						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	315.00	82.60	26019.00
2	2	Erection	Kg	315.00	4.13	1300.95
					Total	27319.95
Item- 4 G.I. Gantry Structures						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1000.00	112.10	112100.00
2	2	Erection	Kg	1000.00	5.61	5605.00
					Total	117705.00
Item- 5 G.I.Nut Bolts						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	132.16	13216.00
2	2	Erection	Kg	100.00	6.61	660.80
					Total	13876.80
Item- 6 Welding Rods						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	5000.00	4.72	23600.00
2	2	Erection	Numbers	5000.00	0.24	1180.00
					Total	24780.00
Schedule Schedule II-A-I : 10) Earthing work						
Item- 1 M.S. Flats(50 X 10mm)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	50.00	76.70	3835.00
2	2	Erection	Kg	50.00	3.84	192.00
					Total	4027.00
Item- 2 M.S.Flat 25x6 mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	20.00	76.70	1534.00
2	2	Erection	Kg	20.00	3.84	76.80
					Total	1610.80
Item- 3 Earthing Sets H.T of C.I.pipe 150 mm 3 mtr.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	8678.90	8678.90
2	2	Erection	Numbers	1.00	433.95	433.95
					Total	9112.85
Item- 4 Coal						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	20.06	2006.00
2	2	Erection	Kg	100.00	1.00	100.00
					Total	2106.00
Item- 5 Salt						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	14.16	1416.00
2	2	Erection	Kg	100.00	0.71	70.80
					Total	1486.80
Item- 6 Welding Rods						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Numbers	50.00	4.72	236.00
2	2	Erection	Numbers	50.00	0.24	12.00
					Total	248.00
Item- 7	Hiring of Welding machine					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	323.32	323.32
2	2	Erection	Numbers	1.00	16.17	16.17
					Total	339.49
Item- 8	Brick & Masonary works for earthing pit					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	2375.34	2375.34
2	2	Erection	Numbers	1.00	118.77	118.77
					Total	2494.11
Schedule	Schedule II-C-I : LAYING OF 33 KV UNDER GROUND CABLE FOR Railway Crossing One+One (Spare) Cable - 3 Locations Total: 2*304=608 Rmt					
Item- 1	XLPE Cable 33 KV, 3 C / 300 mm sq.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	608.00	2571.22	1563301.76
2	2	Erection	RM	608.00	385.68	234495.26
					Total	1797797.02
Item- 2	HDPE/GI Pipe					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	164.00	1239.00	203196.00
2	2	Erection	Metre	164.00	185.85	30479.40
					Total	233675.40
Item- 3	G. I. Pipe 110 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	36.00	378.78	13636.08
2	2	Erection	Metre	36.00	56.82	2045.52
					Total	15681.60
Item- 4	HT Earthing For Cable					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	545.16	3270.96
2	2	Erection	Numbers	6.00	81.77	490.62
					Total	3761.58
Item- 5	33 kV Heat shrink Outdoor termination joint (Al) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	12.00	23351.02	280212.24
2	2	Erection	Numbers	12.00	3502.65	42031.80
					Total	322244.04
Item- 6	Sand					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	45.00	330.40	14868.00
2	2	Erection	cm	45.00	49.56	2230.20
					Total	17098.20
Item- 7	Misc. For XLPE U/G Cable					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	6.00	1239.00	7434.00
2	2	Erection	Lumpsum	6.00	185.85	1115.10

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	8549.10
Item- 8	33 KV LA 9 KA					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	3.00	13906.30	41718.90
2	2	Erection	Set	3.00	2085.95	6257.85
					Total	47976.75
Item- 9	RCC Tiles (0.6 x 0.5) Mtrs.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	360.00	175.82	63295.20
2	2	Erection	Numbers	360.00	26.37	9494.28
					Total	72789.48
Schedule	Schedule II-D-I : 33 KV S/C Line Suspension type with 100 mm ² AAAC lines on 152 X 152 mm 13 mtr. RSJ: 5.4 Km.					
Item- 1	RSJ 152x152, 13 m long					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	55.00	34348.62	1889174.10
2	2	Erection	Numbers	55.00	5152.29	283375.95
					Total	2172550.05
Item- 2	RSJ 116x100, 11 m long (For Stud)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	12.00	18018.60	216223.20
2	2	Erection	Numbers	12.00	2702.79	32433.48
					Total	248656.68
Item- 3	MS Channel 100x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	2673.00	82.60	220789.80
2	2	Erection	Kg	2673.00	12.39	33118.47
					Total	253908.27
Item- 4	M.S.Channel 75x40x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	492.00	82.60	40639.20
2	2	Erection	Kg	492.00	12.39	6095.88
					Total	46735.08
Item- 5	MS angle 50x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1100.00	82.60	90860.00
2	2	Erection	Kg	1100.00	12.39	13629.00
					Total	104489.00
Item- 6	MS Flat 75x10 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	480.00	77.27	37089.60
2	2	Erection	Kg	480.00	11.59	5563.20
					Total	42652.80
Item- 7	G.I.Nut Bolts					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	432.00	132.16	57093.12
2	2	Erection	Kg	432.00	19.82	8562.24
					Total	65655.36
Item- 8	Disc Insulator 11 KV 70 KN					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	639.00	384.68	245810.52
2	2	Erection	Numbers	639.00	57.70	36871.58
					Total	282682.10
Item- 9 SSN Hardware for 0.1 Dog or AAAC 100 Sq.mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	117.00	304.44	35619.48
2	2	Erection	Numbers	117.00	45.67	5343.39
					Total	40962.87
Item- 10 Strain Hardware for Dog0.1 or Equ.AAAC.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	96.00	436.60	41913.60
2	2	Erection	Numbers	96.00	65.49	6287.04
					Total	48200.64
Item- 11 AAAC 100 mm2						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	17010.00	82.60	1405026.00
2	2	Erection	Metre	17010.00	12.39	210753.90
					Total	1615779.90
Item- 12 H.T.Stay Set						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	32.00	952.61	30483.52
2	2	Erection	Numbers	32.00	142.89	4572.48
					Total	35056.00
Item- 13 G.I.Stay Wire 7/4mm(8 SWG)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	320.00	84.96	27187.20
2	2	Erection	Kg	320.00	12.74	4078.08
					Total	31265.28
Item- 14 G.I.Wire 8 SWG/ 6 SWG						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	702.00	84.96	59641.92
2	2	Erection	Kg	702.00	12.74	8946.29
					Total	68588.21
Item- 15 Sleeve joints						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	16.00	185.26	2964.16
2	2	Erection	Numbers	16.00	27.79	444.64
					Total	3408.80
Item- 16 Danger Board in yard.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	55.00	102.66	5646.30
2	2	Erection	Numbers	55.00	15.40	847.00
					Total	6493.30
Item- 17 Earthing Sets H.T						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	55.00	545.16	29983.80
2	2	Erection	Numbers	55.00	81.77	4497.35

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

						Total	34481.15
Item- 18	Concreting ration 1:3:6						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	cm	109.80	5107.04	560752.99	
2	2	Erection	cm	109.80	766.06	84113.39	
						Total	644866.38
Item- 19	G.I.Barbed Wire 'A' type.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Kg	324.00	94.80	30715.20	
2	2	Erection	Kg	324.00	14.22	4607.28	
						Total	35322.48
Item- 20	Black bituminus paint						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Litre	32.40	177.00	5734.80	
2	2	Erection	Litre	32.40	26.55	860.22	
						Total	6595.02
Item- 21	Red Oxide Paint for 2 coats						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Litre	108.00	146.32	15802.56	
2	2	Erection	Litre	108.00	21.95	2370.60	
						Total	18173.16
Item- 22	Aluminium Paint for 1 coat						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Litre	48.60	306.80	14910.48	
2	2	Erection	Litre	48.60	46.02	2236.57	
						Total	17147.05
Item- 23	Sundries						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Lumpsum	16.20	1045.48	16936.78	
2	2	Erection	Lumpsum	16.20	156.82	2540.48	
						Total	19477.26
Item- 24	Wedge connectors :DOG TO DOG or equivalent AAAC						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Numbers	96.00	758.01	72768.96	
2	2	Erection	Numbers	96.00	113.70	10915.20	
						Total	83684.16
Schedule	Schedule II-B-I : Cost Data for laying of 33 KV 3 C 300 mm 2 XLPE under ground Cable for 4 nos locations at Tower Line/Road/Alongwith Railway Line: 2.376 Km (With Standby)						
Item- 1	XLPE Cable 33 KV, 3 C / 300 mm sq.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	RM	2376.00	2571.22	6109218.72	
2	2	Erection	RM	2376.00	385.68	916382.81	
						Total	7025601.53
Item- 2	R.C.C. Pipe 150 mm 2 M						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
1	1	Supply	Numbers	50.00	742.22	37111.00	
2	2	Erection	Numbers	50.00	111.33	5566.50	
						Total	42677.50
Item- 3	RCC Tiles (0.6 x 0.5) Mtrs.						

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2024.00	175.82	355859.68
2	2	Erection	Numbers	2024.00	26.37	53378.95
					Total	409238.63
Item- 4	33 kV Heat shrink Straight through joint (Al) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	45283.68	90567.36
2	2	Erection	Numbers	2.00	6792.55	13585.10
					Total	104152.46
Item- 5	33 kV Heat shrink Outdoor termination joint (Al) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	16.00	23351.02	373616.32
2	2	Erection	Numbers	16.00	3502.65	56042.40
					Total	429658.72
Item- 6	Sand					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	248.00	330.40	81939.20
2	2	Erection	cm	248.00	49.56	12290.88
					Total	94230.08
Item- 7	HDPE/GI Pipe					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	48.00	1239.00	59472.00
2	2	Erection	Metre	48.00	185.85	8920.80
					Total	68392.80
Item- 8	Earthing Sets H.T					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	32.00	545.16	17445.12
2	2	Erection	Numbers	32.00	81.77	2616.64
					Total	20061.76
Item- 9	33 KV Lightning Arrestors (Station type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	4.00	17998.54	71994.16
2	2	Erection	Set	4.00	2699.78	10799.12
					Total	82793.28
Item- 10	Misc. for XLPE U/G Cable					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	1.00	1357.00	1357.00
2	2	Erection	Lumpsum	1.00	203.55	203.55
					Total	1560.55
Schedule	Schedule II-A-I : 9-b) Foundation (Civil works)					
Item- 1	Foundation for 33 kV Isolators with EB					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 2	Foundation for 33 kV Isolators without EB					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	2	Erection	cm	1.30	389.64	506.53
Total					10637.07	
Item- 3	Foundation for 33 kV C.Ts					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
Total					10637.07	
Item- 4	Foundation for 33 kV P.Ts					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
Total					10637.07	
Item- 5	Foundation for 33 kV Lightning Arrestor					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
Total					10637.07	
Item- 6	Foundation for 33 kV Breaker					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
Total					10637.07	
Item- 7	Foundation for Gantry Structures					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	2.60	7792.72	20261.07
2	2	Erection	cm	2.60	389.64	1013.06
Total					21274.13	
Schedule	Schedule II-A-I : 9-c) Bus-Bar Material					
Item- 1	AAAC 232 mm2					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	25.00	191.16	4779.00
2	2	Erection	Metre	25.00	9.56	239.00
Total					5018.00	
Item- 2	Wedge Connectors : T-Connector for 200 sq mm conductor(Compression type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	30.00	4548.90	136467.00
2	2	Erection	Numbers	30.00	227.44	6823.20
Total					143290.20	
Item- 3	Breaker Clamps					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	2290.38	13742.28
2	2	Erection	Numbers	6.00	114.52	687.12
Total					14429.40	
Item- 4	clamps for Isolator					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	12.00	1146.96	13763.52
2	2	Erection	Numbers	12.00	57.35	688.20
Total					14451.72	

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 5 Clamps for CTs						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	1601.26	9607.56
2	2	Erection	Numbers	6.00	80.06	480.36
					Total	10087.92
Item- 6 Disc Insulator 11 KV 70 KN						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	18.00	384.68	6924.24
2	2	Erection	Numbers	18.00	19.23	346.14
					Total	7270.38
Item- 7 Strain Hardware for AAAC232 sq.mm.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	817.74	4906.44
2	2	Erection	Numbers	6.00	40.89	245.34
					Total	5151.78
Schedule Schedule II-A-I : 9-e) Painting of Structure						
Item- 1 Red Oxide Paint for 2 coats						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	10.00	146.32	1463.20
2	2	Erection	Litre	10.00	7.32	73.20
					Total	1536.40
Item- 2 Aluminium Paint for 1 coat						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	5.00	306.80	1534.00
2	2	Erection	Litre	5.00	15.34	76.70
					Total	1610.70
Schedule Schedule II-G-I : Supply & fixing of AMR Modem						
Item- 1 Supply & Fixing of Modem along with hardware accessories such as antenna, connectors, RS232 cable for connecting modem to meter. Configuration of Modem, Insertion of SIMcard & Confirmation of connectivity between MSEDCL MDAS & AMR end point, complete meter data availability in MSEDCL MDAS through Modem.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	3432.38	10297.14
2	2	Erection	Numbers	3.00	171.62	514.86
					Total	10812.00
Schedule Schedule II-F-I : Meter cubical for check & Main Meter						
Item- 1 XLPE Cable 33 KV, 3C/300 mm sq.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	240.00	2571.22	617092.80
2	2	Erection	Metre	240.00	385.68	92563.92
					Total	709656.72
Item- 2 Half round cement pipe (150mm X 1mtr)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	140.00	742.22	103910.80
2	2	Erection	Numbers	140.00	111.33	15586.62
					Total	119497.42
Item- 3 RCC Tiles (0.6 x 0.5) Mtrs.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	416.00	175.82	73141.12

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	2	Erection	Numbers	416.00	26.37	10971.17
					Total	84112.29
Item- 4	33 kV Heat shrink Outdoor termination joint (AI) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	16.00	23351.02	373616.32
2	2	Erection	Numbers	16.00	3502.65	56042.40
					Total	429658.72
Item- 5	33 KV Metering Cubicle with metering CTs: Single Core Single Ratio: 100/5A, Class of Accuracy: 0.2s, Burden: 10VA, Confirming to IS-16227(Part I&II) suitable for 33 KV, MSEDCL Approved b) PTs: Single Core Single Ratio: 33KV/3/110V/3, Class of Accuracy: 0.2, Burden: 50VA, Confirming to IS-16227(Part I&II) suitable for 33 KV, MSEDCL Approved at Consumer End AND At both Source end i.e. at 132/33 KV Deepnagar SS and 33/11 KV Tapi nagar SS at C&R Panel, the HT TOD KVAH compatible Meters(Lead+Lag), Category-C1,15 Minute DIP is proposed					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	4.00	224200.00	896800.00
2	2	Erection	Set	4.00	33630.00	134520.00
					Total	1031320.00
Item- 6	33 KV LA 9 KA					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	12.00	13906.30	166875.60
2	2	Erection	Set	12.00	2085.95	25031.40
					Total	191907.00
Item- 7	Foundation for L.A.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	10.40	516.84	5375.14
2	2	Erection	cm	10.40	77.53	806.31
					Total	6181.45
Item- 8	Structure for L.A.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1000.00	82.60	82600.00
2	2	Erection	Kg	1000.00	12.39	12390.00
					Total	94990.00
Item- 9	Misc. Material					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	4.00	5900.00	23600.00
2	2	Erection	Lumpsum	4.00	885.00	3540.00
					Total	27140.00
Item- 10	Copper flat 25 x3 mm for earthing					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	240.00	824.82	197956.80
2	2	Erection	Kg	240.00	123.72	29693.52
					Total	227650.32
Item- 11	Copper Plate 4 mm thickness for earthing					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	120.00	824.82	98978.40
2	2	Erection	Kg	120.00	123.72	14846.76
					Total	113825.16
Item- 12	Earthing GI Pipes HT (One complete earthing for LA)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	40.00	463.56	18542.52

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	2	Erection	Numbers	40.00	69.53	2781.36
Total						21323.88
Item- 13	Bentonite Clay					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	360.00	17.64	6350.76
2	2	Erection	Kg	360.00	2.65	952.56
Total						7303.32
Item- 14	Charcol Powder					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1440.00	20.36	29311.20
2	2	Erection	Kg	1440.00	3.05	4396.32
Total						33707.52
Item- 15	Raw Salt					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1440.00	14.16	20390.40
2	2	Erection	Kg	1440.00	2.12	3058.56
Total						23448.96
Schedule	Schedule II-E-I : DOUPLE POLE STRUCTURE(cut point) OF- 33 KV LINE USING13 M LONG RSJ POLE with 33 KV Isolators with EB (800 A)					
Item- 1	RSJ 152x152, 13 m long					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	34348.62	1648733.76
2	2	Erection	Numbers	48.00	5152.29	247309.92
Total						1896043.68
Item- 2	RSJ 116x100, 11 m long (For Stud)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	32.00	18018.60	576595.20
2	2	Erection	Numbers	32.00	2702.79	86489.28
Total						663084.48
Item- 3	M.S. Flats(50 X 10mm)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	240.00	77.27	18544.80
2	2	Erection	Kg	240.00	11.59	2781.60
Total						21326.40
Item- 4	MS Channel 100x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1104.00	82.60	91190.40
2	2	Erection	Kg	1104.00	12.39	13678.56
Total						104868.96
Item- 5	MS angle 50x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1200.00	82.60	99120.00
2	2	Erection	Kg	1200.00	12.39	14868.00
Total						113988.00
Item- 6	33 kv guarding channel MS100x50					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1920.00	82.60	158592.00
2	2	Erection	Kg	1920.00	12.39	23788.80
Total						182380.80

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 7 33 kV Pin Insulators with G.I. Pins						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	72.00	545.75	39294.00
2	2	Erection	Numbers	72.00	81.86	5893.92
					Total	45187.92
Item- 8 Strain Hardware for Dog0.1 or Equ.AAAC.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	144.00	436.60	62870.40
2	2	Erection	Numbers	144.00	65.49	9430.56
					Total	72300.96
Item- 9 Disc Insulator 11 KV 70 KN						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	432.00	384.68	166181.76
2	2	Erection	Numbers	432.00	57.70	24926.40
					Total	191108.16
Item- 10 H.T.Stay Set						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	64.00	952.61	60967.04
2	2	Erection	Numbers	64.00	142.89	9144.96
					Total	70112.00
Item- 11 G.I.Stay Wire 7/4mm(8 SWG)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	640.00	84.96	54374.40
2	2	Erection	Kg	640.00	12.74	8156.16
					Total	62530.56
Item- 12 Earthing Sets H.T						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	545.16	26167.68
2	2	Erection	Numbers	48.00	81.77	3924.96
					Total	30092.64
Item- 13 G.I.Wire 8 SWG/ 6 SWG						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	144.00	84.96	12234.24
2	2	Erection	Kg	144.00	12.74	1835.14
					Total	14069.38
Item- 14 G.I.Barbed Wire 'A' type.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	168.00	94.80	15926.40
2	2	Erection	Kg	168.00	14.22	2388.96
					Total	18315.36
Item- 15 Danger Board in yard.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	102.66	4927.68
2	2	Erection	Numbers	48.00	15.40	739.20
					Total	5666.88
Item- 16 Black Bituminus Paint						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	24.00	177.00	4248.00

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

2	2	Erection	Litre	24.00	26.55	637.20
Total						4885.20
Item- 17	Red Oxide Paint for 2 coats					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	72.00	146.32	10535.04
2	2	Erection	Litre	72.00	21.95	1580.40
Total						12115.44
Item- 18	Aluminium Paint for 1 coat					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	48.00	306.80	14726.40
2	2	Erection	Litre	48.00	46.02	2208.96
Total						16935.36
Item- 19	Concreting ration 1:3:6					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	48.00	5107.04	245137.92
2	2	Erection	cm	48.00	766.06	36770.88
Total						281908.80
Item- 20	33 KV Isolators with EB (800 A)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	7.00	82056.02	574392.14
2	2	Erection	Set	7.00	12308.40	86158.80
Total						660550.94
Item- 21	Sundries					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	24.00	1045.48	25091.52
2	2	Erection	Lumpsum	24.00	156.82	3763.68
Total						28855.20
Schedule	Schedule II-A-I : 33 KV FEEDER BAY With Gantry structure & PT					
Item- 1	33 KV Lightning Arrestors (Station type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	17998.54	17998.54
2	2	Erection	Set	1.00	899.93	899.93
Total						18898.47
Item- 2	33 KV Isolators with EB (800 A)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	82056.02	82056.02
2	2	Erection	Set	1.00	4102.80	4102.80
Total						86158.82
Item- 3	33 KV Isolators without EB (800 Amp.)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	2.00	75098.74	150197.48
2	2	Erection	Set	2.00	3754.94	7509.88
Total						157707.36
Item- 4	33 KV VCB complete 1600 Amp (O.D.)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	292504.30	292504.30
2	2	Erection	Numbers	1.00	14625.22	14625.22
Total						307129.52

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 5 33 KV P.T.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	29400.88	88202.64
2	2	Erection	Numbers	3.00	1470.04	4410.12
					Total	92612.76
Item- 6 CT 200-100/1-1 A , 33 KV						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	36374.68	109124.04
2	2	Erection	Numbers	3.00	1818.73	5456.19
					Total	114580.23
Item- 7 C&R panel for 33 KV for feeder breaker						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	76091.12	76091.12
2	2	Erection	Set	1.00	3804.56	3804.56
					Total	79895.68
Item- 8 Marshalling Box						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	6823.94	6823.94
2	2	Erection	Numbers	1.00	341.20	341.20
					Total	7165.14
Schedule Schedule II-A-I : 9-d) Control Cable						
Item- 1 Armoured Copper control cable 19C X 2.5 Sq mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	50.00	559.32	27966.00
2	2	Erection	RM	50.00	27.97	1398.50
					Total	29364.50
Item- 2 Armoured Copper control cable 2Cx2.5 sq.mm.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	40.00	93.22	3728.80
2	2	Erection	RM	40.00	4.66	186.40
					Total	3915.20
Item- 3 Armoured Copper control cable 2Cx4 sq.mm.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	50.00	126.26	6313.00
2	2	Erection	RM	50.00	6.31	315.50
					Total	6628.50
Item- 4 Cable Trays 2.5 Mtr. X 6" W						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	451.94	4519.40
2	2	Erection	Numbers	10.00	22.60	226.00
					Total	4745.40
Item- 5 Cable Glands, rerules and tape etc.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	1.00	711.07	711.07
2	2	Erection	Lumpsum	1.00	35.55	35.55
					Total	746.62
Item- 6 Angle for fixing trays 50x50x6mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Kg	20.00	82.60	1652.00
2	2	Erection	Kg	20.00	4.13	82.60
					Total	1734.60
Item- 7 Half round cement pipe (150mm X 1mtr)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	80.00	185.26	14820.80
2	2	Erection	Numbers	80.00	9.26	740.80
					Total	15561.60
Item- 8 Sand						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	4.00	330.40	1321.60
2	2	Erection	cm	4.00	16.52	66.08
					Total	1387.68
Schedule Schedule III-A-II : 33 KV FEEDER BAY With Gantry structure & PT						
Item- 1 33 KV Lightning Arrestors (Station type)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	17998.54	17998.54
2	2	Erection	Set	1.00	899.93	899.93
					Total	18898.47
Item- 2 33 KV Isolators with EB (800 A)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	82056.02	82056.02
2	2	Erection	Set	1.00	4102.80	4102.80
					Total	86158.82
Item- 3 33 KV Isolators without EB (800 Amp.)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	2.00	75098.74	150197.48
2	2	Erection	Set	2.00	3754.94	7509.88
					Total	157707.36
Item- 4 33 KV VCB complete 1600 Amp (O.D.)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	292504.30	292504.30
2	2	Erection	Numbers	1.00	14625.22	14625.22
					Total	307129.52
Item- 5 33 KV P.T.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	29400.88	88202.64
2	2	Erection	Numbers	3.00	1470.04	4410.12
					Total	92612.76
Item- 6 CT 200-100/1-1 A , 33 KV						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	3.00	36374.68	109124.04
2	2	Erection	Numbers	3.00	1818.73	5456.19
					Total	114580.23
Item- 7 C&R panel for 33 KV for feeder breaker						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	76091.12	76091.12
2	2	Erection	Set	1.00	3804.56	3804.56

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	79895.68
Item- 8	Marshalling Box					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	6823.94	6823.94
2	2	Erection	Numbers	1.00	341.20	341.20
					Total	7165.14
Schedule	Schedule III-A-II-9-c : BUS-BAR MATERIAL					
Item- 1	AAAC 232 mm2					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	25.00	191.16	4779.00
2	2	Erection	Metre	25.00	9.56	239.00
					Total	5018.00
Item- 2	Wedge Connectors : T-Connector for 200 sq mm conductor(Compression type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	30.00	4548.90	136467.00
2	2	Erection	Numbers	30.00	227.44	6823.20
					Total	143290.20
Item- 3	Breaker Clamps					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	2290.38	13742.28
2	2	Erection	Numbers	6.00	114.52	687.12
					Total	14429.40
Item- 4	clamps for Isolator					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	12.00	1146.96	13763.52
2	2	Erection	Numbers	12.00	57.35	688.20
					Total	14451.72
Item- 5	Clamps for CTs					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	1601.26	9607.56
2	2	Erection	Numbers	6.00	80.06	480.36
					Total	10087.92
Item- 6	Disc Insulator 11 KV 70 KN					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	18.00	384.68	6924.24
2	2	Erection	Numbers	18.00	19.23	346.14
					Total	7270.38
Item- 7	Strain Hardware for AAAC232 sq.mm.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	6.00	817.74	4906.44
2	2	Erection	Numbers	6.00	40.89	245.34
					Total	5151.78
Schedule	Schedule III-A-II-9-d : CONTROL CABLE					
Item- 1	Armoured Copper control cable 19C X 2.5 Sq mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	50.00	559.32	27966.00
2	2	Erection	RM	50.00	27.97	1398.50
					Total	29364.50

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 2 Armoured Copper control cable 2Cx2.5 sq.mm.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	40.00	93.22	3728.80
2	2	Erection	RM	40.00	4.66	186.40
					Total	3915.20
Item- 3 Armoured Copper control cable 2Cx4 sq.mm.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	50.00	126.26	6313.00
2	2	Erection	RM	50.00	6.31	315.50
					Total	6628.50
Item- 4 Cable Trays 2.5 Mtr. X 6" W						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	10.00	451.94	4519.40
2	2	Erection	Numbers	10.00	22.60	226.00
					Total	4745.40
Item- 5 Cable Glands, rerules and tape etc.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	1.00	711.07	711.07
2	2	Erection	Lumpsum	1.00	35.55	35.55
					Total	746.62
Item- 6 Angle for fixing trays 50x50x6mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	20.00	82.60	1652.00
2	2	Erection	Kg	20.00	4.13	82.60
					Total	1734.60
Item- 7 Half round cement pipe (150mm X 1mtr)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	80.00	185.26	14820.80
2	2	Erection	Numbers	80.00	9.26	740.80
					Total	15561.60
Item- 8 Sand						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	4.00	330.40	1321.60
2	2	Erection	cm	4.00	16.52	66.08
					Total	1387.68
Schedule Schedule III-A-II-9-b : FOUNDATION(Civil works)						
Item- 1 Foundation for 33 kV Isolators with EB						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 2 Foundation for 33 kV Isolators without EB						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 3 Foundation for 33 kV C.Ts						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 4	Foundation for 33 kV P.Ts					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 5	Foundation for 33 kV Lightning Arrestor					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 6	Foundation for 33 kV Breaker					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	1.30	7792.72	10130.54
2	2	Erection	cm	1.30	389.64	506.53
					Total	10637.07
Item- 7	Foundation for Gantry Structures					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	2.60	7792.72	20261.07
2	2	Erection	cm	2.60	389.64	1013.06
					Total	21274.13
Schedule	Schedule III-B-II : Laying of 1 Km. 33 KV 3 C 300 mm 2 XLPE under ground Cable for 4 nos locations at Tower Line/Road/Along with Railway Line: 2.376 Km (With Standby)					
Item- 1	XLPE Cable 33 KV, 3 C / 300 mm sq.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	RM	1000.00	2571.22	2571220.00
2	2	Erection	RM	1000.00	385.68	385683.00
					Total	2956903.00
Item- 2	R.C.C. Pipe 150 mm 2 M					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	30.00	742.22	22266.60
2	2	Erection	Numbers	30.00	111.33	3339.90
					Total	25606.50
Item- 3	RCC Tiles (0.6 x 0.5) Mtrs.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	940.00	175.82	165270.80
2	2	Erection	Numbers	940.00	26.37	24790.62
					Total	190061.42
Item- 4	33 kV Heat shrink Straight through joint (Al) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	2.00	45283.68	90567.36
2	2	Erection	Numbers	2.00	6792.55	13585.10
					Total	104152.46
Item- 5	33 kV Heat shrink Outdoor termination joint (Al) kit for XLPE 3 C X 300 sqmm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	16.00	23351.02	373616.32
2	2	Erection	Numbers	16.00	3502.65	56042.40

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	429658.72
Item- 6	Sand					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	250.00	330.40	82600.00
2	2	Erection	cm	250.00	49.56	12390.00
					Total	94990.00
Item- 7	HDPE/GI Pipe					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	164.00	1239.00	203196.00
2	2	Erection	Metre	164.00	185.85	30479.40
					Total	233675.40
Item- 8	Earthing Sets H.T					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	4.00	545.16	2180.64
2	2	Erection	Numbers	4.00	81.77	327.08
					Total	2507.72
Item- 9	33 KV Lightning Arrestors (Station type)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	1.00	17998.54	17998.54
2	2	Erection	Set	1.00	2699.78	2699.78
					Total	20698.32
Item- 10	Misc. for XLPE U/G Cable					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	1.00	1357.00	1357.00
2	2	Erection	Lumpsum	1.00	203.55	203.55
					Total	1560.55
Schedule	Schedule III-D-II : DOUPLE POLE STRUCTURE(cut point) OF- 33 KV LINE USING13 M LONG RSJ POLE with 33 KV Isolators with EB (800 A)					
Item- 1	RSJ 152x152, 13 m long					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	34348.62	1648733.76
2	2	Erection	Numbers	48.00	5152.29	247309.92
					Total	1896043.68
Item- 2	RSJ 116x100, 11 m long (For Stud)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	32.00	18018.60	576595.20
2	2	Erection	Numbers	32.00	2702.79	86489.28
					Total	663084.48
Item- 3	M.S. Flats(50 X 10mm)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	240.00	77.27	18544.80
2	2	Erection	Kg	240.00	11.59	2781.60
					Total	21326.40
Item- 4	MS Channel 100x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1104.00	82.60	91190.40
2	2	Erection	Kg	1104.00	12.39	13678.56
					Total	104868.96
Item- 5	MS angle 50x50x6 mm					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1200.00	82.60	99120.00
2	2	Erection	Kg	1200.00	12.39	14868.00
					Total	113988.00
Item- 6		33 kv guarding channel MS100x50				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1920.00	82.60	158592.00
2	2	Erection	Kg	1920.00	12.39	23788.80
					Total	182380.80
Item- 7		33 kV Pin Insulators with G.I. Pins				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	72.00	545.75	39294.00
2	2	Erection	Numbers	72.00	81.86	5893.92
					Total	45187.92
Item- 8		Strain Hardware for Dog0.1 or Equ.AAAC.				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	144.00	436.60	62870.40
2	2	Erection	Numbers	144.00	65.49	9430.56
					Total	72300.96
Item- 9		Disc Insulator 11 KV 70 KN				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	432.00	384.68	166181.76
2	2	Erection	Numbers	432.00	57.70	24926.40
					Total	191108.16
Item- 10		H.T.Stay Set				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	64.00	952.61	60967.04
2	2	Erection	Numbers	64.00	142.89	9144.96
					Total	70112.00
Item- 11		G.I.Stay Wire 7/4mm(8 SWG)				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	640.00	84.96	54374.40
2	2	Erection	Kg	640.00	12.74	8156.16
					Total	62530.56
Item- 12		Earthing Sets H.T				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	545.16	26167.68
2	2	Erection	Numbers	48.00	81.77	3924.96
					Total	30092.64
Item- 13		G.I.Wire 8 SWG/ 6 SWG				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	144.00	84.96	12234.24
2	2	Erection	Kg	144.00	12.74	1835.14
					Total	14069.38
Item- 14		G.I.Barbed Wire 'A' type.				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	168.00	94.80	15926.40
2	2	Erection	Kg	168.00	14.22	2388.96

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

					Total	18315.36
Item- 15	Danger Board in yard.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	48.00	102.66	4927.68
2	2	Erection	Numbers	48.00	15.40	739.20
					Total	5666.88
Item- 16	Black Bituminus Paint					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	24.00	177.00	4248.00
2	2	Erection	Litre	24.00	26.55	637.20
					Total	4885.20
Item- 17	Red Oxide Paint for 2 coats					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	72.00	146.32	10535.04
2	2	Erection	Litre	72.00	21.95	1580.40
					Total	12115.44
Item- 18	Aluminium Paint for 1 coat					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	48.00	306.80	14726.40
2	2	Erection	Litre	48.00	46.02	2208.96
					Total	16935.36
Item- 19	Concreting ration 1:3:6					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	48.00	5107.04	245137.92
2	2	Erection	cm	48.00	766.06	36770.88
					Total	281908.80
Item- 20	33 KV Isolators with EB (800 A)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Set	7.00	82056.02	574392.14
2	2	Erection	Set	7.00	12308.40	86158.80
					Total	660550.94
Item- 21	Sundries					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	24.00	1045.48	25091.52
2	2	Erection	Lumpsum	24.00	156.82	3763.68
					Total	28855.20
Schedule	Schedule III-A-II-9-a : STRUCTURE					
Item- 1	Structure for 33 KV L.A.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	250.00	82.60	20650.00
2	2	Erection	Kg	250.00	4.13	1032.50
					Total	21682.50
Item- 2	Structure for 33 KV CT					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	315.00	82.60	26019.00
2	2	Erection	Kg	315.00	4.13	1300.95
					Total	27319.95
Item- 3	Structure for 33 KV PT					

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	315.00	82.60	26019.00
2	2	Erection	Kg	315.00	4.13	1300.95
					Total	27319.95
Item- 4	G.I. Gantry Structures					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	1000.00	112.10	112100.00
2	2	Erection	Kg	1000.00	5.61	5605.00
					Total	117705.00
Item- 5	G.I.Nut Bolts					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	132.16	13216.00
2	2	Erection	Kg	100.00	6.61	660.80
					Total	13876.80
Item- 6	Welding Rods					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	5000.00	4.72	23600.00
2	2	Erection	Numbers	5000.00	0.24	1180.00
					Total	24780.00
Schedule	Schedule III-C-II : Cost data for 33 KV S/C Line Suspension type with100 mm2 AAAC lines on 152 X 152 mm 13 mtr. RSJ: 6.6 Km.					
Item- 1	RSJ 152x152, 13 m long					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	66.00	34348.62	2267008.92
2	2	Erection	Numbers	66.00	5152.29	340051.14
					Total	2607060.06
Item- 2	RSJ 116x100, 11 m long (For Stud)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	9.00	18018.60	162167.40
2	2	Erection	Numbers	9.00	2702.79	24325.11
					Total	186492.51
Item- 3	MS Channel 100x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	2334.00	82.60	192788.40
2	2	Erection	Kg	2334.00	12.39	28918.26
					Total	221706.66
Item- 4	M.S.Channel 75x40x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	429.00	82.60	35435.40
2	2	Erection	Kg	429.00	12.39	5315.31
					Total	40750.71
Item- 5	MS angle 50x50x6 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	957.00	82.60	79048.20
2	2	Erection	Kg	957.00	12.39	11857.23
					Total	90905.43
Item- 6	MS Flat 75x10 mm					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Kg	420.00	77.27	32453.40
2	2	Erection	Kg	420.00	11.59	4867.80
					Total	37321.20
Item- 7 G.I.Nut Bolts						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	377.00	132.16	49824.32
2	2	Erection	Kg	377.00	19.82	7472.14
					Total	57296.46
Item- 8 Disc Insulator 11 KV 70 KN						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	721.00	384.68	277354.28
2	2	Erection	Numbers	721.00	57.70	41603.14
					Total	318957.42
Item- 9 SSN Hardware for 0.1 Dog or AAAC 100 Sq.mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	156.00	304.44	47492.64
2	2	Erection	Numbers	156.00	45.67	7124.52
					Total	54617.16
Item- 10 Strain Hardware for Dog0.1 or Equ.AAAC.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	85.00	436.60	37111.00
2	2	Erection	Numbers	85.00	65.49	5566.65
					Total	42677.65
Item- 11 AAAC 100 mm2						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Metre	14850.00	82.60	1226610.00
2	2	Erection	Metre	14850.00	12.39	183991.50
					Total	1410601.50
Item- 12 H.T.Stay Set						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	28.00	952.61	26673.08
2	2	Erection	Numbers	28.00	142.89	4000.92
					Total	30674.00
Item- 13 G.I.Stay Wire 7/4mm(8 SWG)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	283.00	84.96	24043.68
2	2	Erection	Kg	283.00	12.74	3606.55
					Total	27650.23
Item- 14 G.I.Wire 8 SWG/ 6 SWG						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	613.00	84.96	52080.48
2	2	Erection	Kg	613.00	12.74	7812.07
					Total	59892.55
Item- 15 Sleeve Joints						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	14.00	185.26	2593.64
2	2	Erection	Numbers	14.00	27.79	389.06
					Total	2982.70

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

Item- 16 Danger Board in yard.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	66.00	102.66	6775.56
2	2	Erection	Numbers	66.00	15.40	1016.40
					Total	7791.96
Item- 17 Earthing Sets H.T						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	66.00	545.16	35980.56
2	2	Erection	Numbers	66.00	81.77	5396.82
					Total	41377.38
Item- 18 Concreting ration 1:3:6						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	cm	118.00	5107.04	602630.72
2	2	Erection	cm	118.00	766.06	90395.08
					Total	693025.80
Item- 19 G.I.Barbed Wire 'A' type.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	283.00	94.80	26828.40
2	2	Erection	Kg	283.00	14.22	4024.26
					Total	30852.66
Item- 20 Black bituminus paint						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	28.00	177.00	4956.00
2	2	Erection	Litre	28.00	26.55	743.40
					Total	5699.40
Item- 21 Red Oxide Paint for 2 coats						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	94.00	146.32	13754.08
2	2	Erection	Litre	94.00	21.95	2063.30
					Total	15817.38
Item- 22 Aluminium Paint for 1 coat						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	42.00	306.80	12885.60
2	2	Erection	Litre	42.00	46.02	1932.84
					Total	14818.44
Item- 23 Sundries						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Lumpsum	14.00	1045.48	14636.72
2	2	Erection	Lumpsum	14.00	156.82	2195.48
					Total	16832.20
Item- 24 Wedge connectors : DOG TO DOG or equivalent AAAC						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	85.00	758.01	64430.85
2	2	Erection	Numbers	85.00	113.70	9664.50
					Total	74095.35
Schedule Schedule III-A-II-9-e : PAINTING OF STRUCTURE						
Item- 1 Red Oxide Paint for 2 coats						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

1	1	Supply	Litre	10.00	146.32	1463.20
2	2	Erection	Litre	10.00	7.32	73.20
					Total	1536.40
Item- 2 Aluminium Paint for 1 coat						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Litre	5.00	306.80	1534.00
2	2	Erection	Litre	5.00	15.34	76.70
					Total	1610.70
Schedule Schedule III-A-II-10 : EARTHING WORK						
Item- 1 M.S. Flats(50 X 10mm)						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	50.00	76.70	3835.00
2	2	Erection	Kg	50.00	3.84	192.00
					Total	4027.00
Item- 2 M.S.Flat 25x6 mm						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	20.00	76.70	1534.00
2	2	Erection	Kg	20.00	3.84	76.80
					Total	1610.80
Item- 3 Earthing Sets H.T of C.I.pipe 150 mm 3 mtr.						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	8678.90	8678.90
2	2	Erection	Numbers	1.00	433.95	433.95
					Total	9112.85
Item- 4 Coal						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	20.06	2006.00
2	2	Erection	Kg	100.00	1.00	100.00
					Total	2106.00
Item- 5 Salt						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Kg	100.00	14.16	1416.00
2	2	Erection	Kg	100.00	0.71	70.80
					Total	1486.80
Item- 6 Welding Rods						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	50.00	4.72	236.00
2	2	Erection	Numbers	50.00	0.24	12.00
					Total	248.00
Item- 7 Hiring of Welding machine						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	323.32	323.32
2	2	Erection	Numbers	1.00	16.17	16.17
					Total	339.49
Item- 8 Brick & Masonary works for earthing pit						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply	Numbers	1.00	2375.34	2375.34
2	2	Erection	Numbers	1.00	118.77	118.77

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

	Total	2494.11
--	--------------	----------------

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB(available in GCC), along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)
1.1	Calculation of required minimum average annual contractual turnover:- V=Rs. 80509760, N=9 months = 0.75 years, V/N=Rs. 80509760/0.75 =RS. 107346347, V is less than V/N, Hence, required minimum average annual contractual turnover = Rs. 80509760	No	No	Not Allowed

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender. Note: (1) Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate	No	No	Allowed (Mandatory)
1.1	Definition of Similar Nature of Works :- Repair/Overhauling/SITC (Supply, Installation, Testing, Commissioning) of any one or combination of the following: i. HT/LT Transformer & Switchgear. ii. HT/LT Transformer & Panels. iii HT/LT Transformer & Cables. for 11 KV or Higher capacity sub stations.	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The registration of contractors working under Railway departments with ESIC is mandatory (if applicable as per current Law / Act)	No	No	Allowed (Mandatory)
2	In case a tenderer is participating as Sole Proprietor in a tender, it is mandatory for him to submit an undertaking on suitable stamp paper to this effect clearly mentioning PAN number also along with tender document at the time of submission of tender.	No	No	Allowed (Mandatory)
3	The tenderer may submit scanned copy of partnership deed if applicable.	No	No	Allowed (Mandatory)
4	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Contractor shall ensure all precautions during digging work close to Rly signaling, telecom electrical cables etc. Penalties to be imposed for damages to any cable as per Railway board letter no. 2021/Tele/5(2)/3- Part(1)/(3425647) dtd 12.06.2023	No	No	Not Allowed

Special Conditions

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Contractor is to abide by the provisions of Payment of Wages act & Minimum Wages act in terms of clause 54 and 55 of Indian Railways General Condition of Contract. In order to ensure the same, an application has been developed and hosted on website 'www.shramikkalyan.indianrailways.gov.in'. Contractor shall register his firm/company etc. and upload requisite details of labour and their payment in this portal. These details shall be available in public domain. The Registration/ updation of Portal shall be done as under: (a)Contractor shall apply for onetime registration of his company/firm etc. in the Shramikkalyan portal with requisite details subsequent to issue of Letter of Acceptance. Engineer shall approve the contractor's registration in the portal within 7 days of receipt of such request. (b)Contractor once approved by any Engineer, can create password with login ID (PAN No.) for subsequent use of portal for all LoAs issued in his favour. (c)The contractor once registered on the portal, shall provide details of his Letter of Acceptances (LoA) / Contract Agreements on shramikkalyan portal within 15 days of issue of any LoA for approval of concerned engineer. Engineer shall update (if required) and approve the details of LoA filled by contractor within 7 days of receipt of such request. (d)After approval of LoA by Engineer, contractor shall fill the salient details of contract labours engaged in the contract and ensure updating of each wage payment to them on shramikkalyan portal on monthly basis. (e)It shall be mandatory upon the contractor to ensure correct and prompt uploading of all salient details of engaged contractual labour & payments made thereof after each wage period.	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The contractor shall submit self attested copy of valid Electrical Contractor License as per Clause No. 45 IE Rule 1956 along with the offer. The offer will be summarily rejected in absence of valid Electrical Contractor License.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/We have read the Tender document and GCC-April 2022 (along with amendments issued by Railway Board from time to time) and all terms & conditions to tender attached hereto and hereby agree to abide by the said conditions. In submitting the tender it would be deemed that the tenderer has kept himself fully Informed of the provision of the Indian Railways Standard General Conditions of Contract including all corrections and Amendments issued upto date and claim that he is not aware of any amendment or correction slip to the IRSGCC shall not be entertained.	No	No	Not Allowed
2	Before submitting a tender, the tenderer will be deemed to have satisfied himself by actual inspection of the site and locality of the works, that all conditions liable to be encountered during the execution of the works are taken into account and that the rates he enters in the tender forms are adequate and all inclusive to accord with the provisions in Clause-37 of the Standard General Conditions of Contract for the completion of works to the entire satisfaction of the Engineer.	No	No	Not Allowed
3	Full value of the bid security shall stand forfeited without prejudice to any other right or remedies if (i)I/We do not execute the contract documents within seven days after receipt of notice issued by the Railway that such documents are ready (ii)I/We do not commence the work within fifteen days after receipt of orders to that effect.	No	No	Not Allowed

Custom

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / Company / Joint Venture (JV) / Registered Society / Registered Trust / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. The tenderer(s) shall enclose the attested copies of the constitution of their concern as per Clause 14 of GCC April 2022 i.e. 'Documents to be Submitted Along with Tender' (Para 2.0 of "Instructions to tenderers and special condition of contract" of Tender Document), and copy of PAN Card along with their tender. Tender Documents in such cases are to be signed by such persons as may be legally competent to sign them on behalf of the firm, company, association, trust or society, as the case may be.	No	No	Allowed (Mandatory)
2	The tenderer whether sole proprietor / a company or a partnership firm / joint venture (JV) / registered society / registered trust / HUF / LLP etc if they want to act through agent or individual partner(s), should submit along with the tender, a copy of power of attorney duly stamped and authenticated by a Notary Public or by Magistrate in favour of the specific person whether he/they be partner(s) of the firm or any other person, specifically authorizing him/them to sign the tender, submit the tender and further to deal with the Tender/ Contract up to the stage of signing the agreement except in case where such specific person is authorized for above purposes through a provision made in the partnership deed / Memorandum of Understanding / Article of Association /Board resolution, failing which tender shall be summarily rejected. A separate power of attorney duly stamped and authenticated by a Notary Public or by Magistrate in favour of the specific person whether he/they be partner(s) of the firm or any other person, shall be submitted after award of work, specifically authorizing him/them to deal with all other contractual activities subsequent to signing of agreement, if required.	No	No	Allowed (Mandatory)
3	In case of other than Company / Proprietary Firm, Annexure-V(A) (attached in last page of tender document) shall also be submitted by the each member of a Partnership Firm / Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. as the case may be. Non submission of above certificate(s) by the bidder shall result in summarily rejection of his/their bid	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TenderDocument402026.pdf	Tender document
2	GCCApril2022dt.27.04.2022.pdf	GCC 2022
3	ACS1to6ofGCC.pdf	ACS 1 to 6 of GCC 2022
4	ACS7to10ofGCC.pdf	ACS 7 to 10 of GCC 2022
5	ACS-11toGCC2022dt.13.03.2026.pdf	ACS 11 of GCC 2022

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: SANJESH

Designation : Sr.DEE/Gen/BSL

**BHUSAWAL DIVISION-ELECTRICAL/CENTRAL RLY
TENDER DOCUMENT**

Tender No: BSL-L-W-T-40-2026

Closing Date/Time: 03/06/2026 15:00
